

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260128	Call Order: 010	Proposal: T4750	District:04
Counties:	ST LUCIE			
Road Name:	SR 5 (US 1)			
Limits:	FROM MIDWAY RD TO S OF EDWARDS RD			
Project(s):	45108015201(*)	Federal Aid No:	D425084B	
Total Roadway Length:	2.513 Miles	Contract Days:	168	
Total Bridge Length:	0.000 Miles	Letting Date:	01/28/26	
Total Proposal Length:	2.513 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$2,498,790.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of but are not limited to, MOT (standard, barrier, PCMS), erosion control (sediment barrier, inlet protection), and lighting (corridor lighting and intersection retrofit), along State Road 5 (US 1) from Midway Road (MP 8.238) to south of Edwards Road (MP 10.751) for 2.513 miles in the City of Fort Pierce, St. Lucie County.

Call Order: 010 Proposal: T4750

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45108015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45108015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	8,064.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	52,416.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,360.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	168.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	364.000
	0102-115-	TYPE III BARRICADE	ED	728.000
	0104- 10- 3	SEDIMENT BARRIER	LF	365.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	6.000
	0107- 1-	LITTER REMOVAL	AC	52.230
	0107- 2-	MOWING	AC	45.790
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (45108015201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (45108015201)	LS	1.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	10.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	46.000
	0999- 16-	PARTNERING, DO NOT BID (45108015201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45108015201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,467.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	11,546.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	98.000

Call Order: 010 Proposal: T4750

ALT	Item	Description	Unit	Quantity
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	62.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	2,868.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	49,077.000
	0715- 5- 51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	18.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 61-242	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 12' ARM LENGTH	EA	1.000
	0715- 61-342	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 12' ARM LENGTH	EA	1.000
	0715- 61-411	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 8' ARM LENGTH	EA	2.000
	0715- 61-442	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 12' ARM LENGTH	EA	66.000
	0715- 65-266	LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 16' ARM LENGTH	EA	13.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	20.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	83.000
Section 0003 Signalization				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	168.000