

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260930	Call Order: 008	Proposal: T3908	District:03
Counties:	BAY			
Road Name:	SCOTT RD			
Limits:	OVER ECONFINA CREEK, BRIDGE NO 464423			
Project(s):	42623815201(*)	Federal Aid No:	D326011B	
Total Roadway Length:	0.110 Miles	Contract Days:	399	
Total Bridge Length:	0.060 Miles	Letting Date:	09/30/26	
Total Proposal Length:	0.170 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days Flexible	

Proposal Budget Estimate: \$2,700,186.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of replacing the existing low-level bridge including piles, approach slabs and slope protection at existing Scott Road over Econfina Creek, Bridge No. 464423, constructing a new bridge, Bridge No. 464168, with roadway approach reconstruction using asphalt pavement, type E curb and gutter, and guardrail. All work to be done in Bay County.

Call Order: 008 Proposal: T3908

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (42623815201)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	244.200
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	44.600
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	25.400
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	120.700
	0400- 7- 1	BRIDGE DECK GROOVING	SY	474.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	474.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	7.200
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	77,834.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	13,987.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	8,728.000
	0415- 2- 5	STAINLESS REINFORCING STEEL, SUBSTRUCTURE	LB	152.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	24.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	690.000
	0455-115-	PILE REDRIVE	EA	18.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	24.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	6.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	310.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	58.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	122.000
	0521- 5- 58	CONCRETE TRAFFIC RAILING- BRIDGE, CORRAL W/CURB	LF	400.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	18.400
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	812.000

Call Order: 008 Proposal: T3908

ALT	Item	Description	Unit	Quantity
	0530- 4- 6	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 6"	SY	90.000
	0530- 74-	BEDDING STONE	TN	289.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (42623815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42623815201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (42623815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	11,172.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,192.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	314,334.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	798.000
	0102-115-	TYPE III BARRICADE	ED	1,596.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	27.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,706.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	477.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0110- 1- 1	CLEARING & GRUBBING (42623815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	40.000
	0120- 1-	REGULAR EXCAVATION	CY	2,288.100
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,132.500
	0160- 4-	TYPE B STABILIZATION	SY	2,363.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	154.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,848.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	141.200
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	151.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	13.300
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	4.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	4.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	238.000
	0430-611-325	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE	EA	2.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	966.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	112.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	444.000
	0536- 8-111	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-2	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	276.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,743.000
Section 0003 Signing				
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	46.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42623815201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.279

Call Order: 008 Proposal: T3908

ALT	Item	Description	Unit	Quantity
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.279
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.062
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.062