

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251203	Call Order: 004	Proposal: T2A51	District:02
Counties:	DUVAL			
Road Name:	SR 5 (US 1 / PHILIPS HWY)			
Limits:	FROM BAYARD BLVD TO BUSINESS PARK BLVD			
Project(s):	20951445201(*)	Federal Aid No:	D224092B	
Total Roadway Length:	1.948 Miles	Contract Days:	200	
Total Bridge Length:	0.000 Miles	Letting Date:	12/03/25	
Total Proposal Length:	1.948 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days	
Proposal Budget Estimate:	\$5,580,429.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of Milling & Resurfacing, Shoulder Treatment, Drainage Improvements, Curb & Gutters, Traffic Signals, Highway Signing, Sidewalks/Bicycle Path, and other incidental construction on SR 5 (US 1 / Philips Highway) in Duval County from Bayard Blvd to Business Park Blvd.

Call Order: 004 Proposal: T2A51

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (20951445201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (20951445201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (20951445201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,126.000
	0102- 60-	WORK ZONE SIGN	ED	9,298.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,670.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	5,942.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	133.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	794.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	800.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	800.000
	0102-115-	TYPE III BARRICADE	ED	168.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	174.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	174.000
	0107- 1-	LITTER REMOVAL	AC	169.210
	0107- 2-	MOWING	AC	141.890
	0110- 1- 1	CLEARING & GRUBBING (20951445201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	366.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (20951445201)	LS	1.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	8,310.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	15,025.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	13,952.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	54,792.000

Call Order: 004 Proposal: T2A51

ALT	Item	Description	Unit	Quantity
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	7,287.700
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	2,198.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	2,912.700
	0425- 1-515	INLETS, DT BOT, TYPE B, PARTIAL	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	449.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	83.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	203.000
	0527- 2-	DETECTABLE WARNINGS	SF	625.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	9.500
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	12,226.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	120.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	181.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	8.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	8.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	872.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.273
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.081
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	921.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	163.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	3.568
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.964
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	36.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.212
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.056
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.165
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20951445201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	3.372
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	50.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	11.000

Call Order: 004 Proposal: T2A51

ALT	Item	Description	Unit	Quantity
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	5.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	7.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	0700- 3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	7.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	45.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	12.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	24.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,566.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (20951445201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,841.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	419.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	753.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.238
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	99.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	240.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.446
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,064.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	25.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	25.000
	0711- 14-528	THERMOPLASTIC, PREFORMED, 12" WHITE WITH 4" BLACK CONTRAST FOR CROSSWALK ON CONCRETE PAVEMENT, 20"	LF	136.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	3.219
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.276
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	2.327
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.004
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.130
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.163
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.251
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	300.000
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	774.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	790.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000

Call Order: 004 Proposal: T2A51

ALT	Item	Description	Unit	Quantity
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	200.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	17.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	11.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	16.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	6.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	4.000
	0660- 4- 51	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY CABINET EQUIPMENT	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	13.000
	0665- 1- 40	PEDESTRIAN DETECTOR, RELOCATE	EA	1.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	13.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	3.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	3.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	10.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	10.000