

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251203	Call Order: 016	Proposal: T7572	District:07
Counties:	HILLSBOROUGH			
Road Name:	SR 93 (I-275)			
Limits:	FROM WILLOW AVE TO W OF GREEN ST			
Project(s):	45054715201(*)	Federal Aid No:	D725029B	
Project(s):	45054715202	Federal Aid No:	D725029B	
Total Roadway Length:	1.111 Miles	Contract Days:	130	
Total Bridge Length:	0.000 Miles	Letting Date:	12/03/25	
Total Proposal Length:	1.111 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$1,890,005.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of resurfacing, restoration, and rehabilitation (RRR) to the asphalt pavement along SR 93 (I-275) from Willow Ave to W of Green Street, three connecting ramps and guardrail replacement in Hillsborough County.

Call Order: 016 Proposal: T7572

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45054715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45054715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	198.000
	0102- 60-	WORK ZONE SIGN	ED	4,858.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	924.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	396.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,524.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	304.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	3.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	458.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	390.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	390.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	130.000
	0102-115-	TYPE III BARRICADE	ED	78.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	41.000
	0107- 1-	LITTER REMOVAL	AC	31.630
	0107- 2-	MOWING	AC	18.550
	0110- 1- 1	CLEARING & GRUBBING (45054715201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45054715202)	LS	1.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	13,053.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	18,356.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	4,594.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	511.100
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	1,644.200

Call Order: 016 Proposal: T7572

ALT	Item	Description	Unit	Quantity
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	629.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	1,239.600
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	24.900
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	878.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	42.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	2.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	798.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	551.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45054715201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45054715202)	LS	1.000
Section 0002 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.653
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	37.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	10.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	1.000
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	1.000
	0700- 3-106	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 101-200 SF	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	44.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	10.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	1.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	1.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	536.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45054715201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45054715202)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.054
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	188.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	55.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.013
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	36.000

Call Order: 016 Proposal: T7572

ALT	Item	Description	Unit	Quantity
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	38.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	153.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	6.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.215
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.577
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.381
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.131
Section 0003 Intelligent Transportation System				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	130.000