

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261202	Call Order: 009	Proposal: T2A90	District:02
Counties:	NASSAU			
Road Name:	SR 9 (I-95)			
Limits:	FROM DUVAL CO LINE TO S OF SR 200			
Project(s):	42747525201(*)	Federal Aid No:	D226021B	
Total Roadway Length:	1.890 Miles	Contract Days:	180	
Total Bridge Length:	0.060 Miles	Letting Date:	12/02/26	
Total Proposal Length:	1.950 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$6,115,372.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, shoulder treatment, guardrail, and other incidental construction on I-95 (SR 9) from Duval County Line to South of SR 200 in Nassau County.

Call Order: 009 Proposal: T2A90

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	114.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	12.200
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (42747525201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42747525201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,800.000
	0102- 60-	WORK ZONE SIGN	ED	3,660.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	34,720.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	470.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	1,992.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	388.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	560.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	560.000
	0104- 10- 3	SEDIMENT BARRIER	LF	18,396.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	55.000
	0107- 1-	LITTER REMOVAL	AC	316.680
	0107- 2-	MOWING	AC	262.820
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	38,107.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	26,054.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	52,267.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	3,143.800
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	3,554.700
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	10,773.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	3,251.800

Call Order: 009 Proposal: T2A90

ALT	Item	Description	Unit	Quantity
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	93.500
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	511.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	6,425.000
	0536- 5- 1	RUB RAIL FOR GUARDRAIL, SINGLE SIDED RUB RAIL	LF	6,426.000
	0536- 73-	GUARDRAIL REMOVAL	LF	6,931.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	14,258.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	1,750.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.954
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	13.909
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.477
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42747525201)	LS	1.000
Section 0003 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	6.954
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	949.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42747525201)	LS	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	3.477
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	6.954
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	3.477
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	634.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.119
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.239
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.119
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.221
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	238.000
Section 0004 Intelligent Transportation System				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	180.000