

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 013	Proposal: T3A06	District:03
Counties:	ESCAMBIA			
Road Name:	SR 95 (US 29 / N CENTURY BLVD)			
Limits:	FROM POND ST TO ALABAMA STATE LINE			
Project(s):	45105715201(*)	Federal Aid No: D326030B		
Total Roadway Length:	2.307 Miles	Contract Days:	70	
Total Bridge Length:	0.000 Miles	Letting Date:	10/28/26	
Total Proposal Length:	2.307 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days Flexible	
Proposal Budget Estimate:	\$297,810.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of installing midblock crosswalks with traffic separators, construction of sidewalk curb ramps, and signing and pavement markings for SR 95 (US 29) N Century Blvd from Pond Steet to Alabama State Line in Escambia County.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 013 Proposal: T3A06

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45105715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45105715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,360.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,916.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	96.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	280.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	154.000
	0104- 10- 3	SEDIMENT BARRIER	LF	95.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0107- 1-	LITTER REMOVAL	AC	2.120
	0107- 2-	MOWING	AC	1.050
	0110- 1- 1	CLEARING & GRUBBING (45105715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	60.000
	0120- 1-	REGULAR EXCAVATION	CY	13.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	76.000
	0520- 5- 46	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 8.5' WIDE	LF	148.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	63.000
	0527- 2-	DETECTABLE WARNINGS	SF	97.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	23.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.489
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45105715201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	12.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700-142-111	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	4.000
	0700-142-122	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/2 BEACONS, 12-20 SF OF STATIC SIGN PANELS	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	20.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	194.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	97.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	120.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.076
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.053
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	565.000