

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250827	Call Order: 004	Proposal: T3930	District:03
Counties:	ESCAMBIA			
Road Name:	SR 295			
Limits:	FROM N OF SR 292 (BARRANCAS AVE) TO SR 727/295			
Project(s):	40901325201(*)	Federal Aid No:	D325021B	
Project(s):	40901325202	Federal Aid No:	N/A	
Project(s):	40901325203	Federal Aid No:	N/A	
Total Roadway Length:	3.674 Miles	Contract Days:	510	
Total Bridge Length:	0.112 Miles	Letting Date:	08/27/25	
Total Proposal Length:	3.786 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$9,655,210.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of resurfacing SR 295 from North of SR 292 (Barrancas Avenue) to SR 727/295 in Escambia County. Existing travel lanes, auxiliary lanes, median crossovers, and paved shoulders will be resurfaced. Existing concrete travel lanes shall be rehabilitated with sealant and restriped. Additional improvements include reconstruction of the traffic signal at the Walmart intersection, intersection and corridor lighting, and ADA enhancements. Financial Project ID 409013-2-52-01 includes the resurfacing and general improvements, 409013-2-52-02 includes the utility work by highway contractor & 409013-2-52-03 includes polymer nosing work. Includes bridge numbers 480052, 480089, 480138, & 480134.

Call Order: 004 Proposal: T3930

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	364.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	44.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (40901325201)	LS	1.000
	0101- 1-	MOBILIZATION (40901325203)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (40901325201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (40901325203)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (40901325201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	456.000
	0102- 60-	WORK ZONE SIGN	ED	75,740.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	116,392.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	117,750.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	510.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	4,198.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	2,550.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,550.000
	0102-115-	TYPE III BARRICADE	ED	2,850.000
	0104- 10- 3	SEDIMENT BARRIER	LF	21,657.000

Call Order: 004 Proposal: T3930

ALT	Item	Description	Unit	Quantity
	0104- 18-	INLET PROTECTION SYSTEM	EA	157.000
	0107- 1-	LITTER REMOVAL	AC	578.140
	0107- 2-	MOWING	AC	578.140
	0110- 1- 1	CLEARING & GRUBBING (40901325201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,036.000
	0120- 1-	REGULAR EXCAVATION	CY	288.200
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	680.800
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	390.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	94,181.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	65,394.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	32.100
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	7,770.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	13,197.100
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	20,225.000
	0350- 6-	CLEANING & SEALING RANDOM CRACKS- CONCRETE PAVEMENT	LF	196.000
	0425- 5-	MANHOLE, ADJUST	EA	18.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	3.000
	0425- 6-	VALVE BOXES, ADJUST	EA	5.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	6.000
	0430-518-102	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ELLIPTICAL	EA	1.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY, 42" TYPE 1	LF	98.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	930.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,143.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	179.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	210.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	6.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	407.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	689.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	4.000
	0527- 2-	DETECTABLE WARNINGS	SF	2,774.000
	0542- 70-	BUMPER GUARDS, CONCRETE	EA	52.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	15,094.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,117.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	19.782
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.243
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	6,388.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,884.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,494.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	12.532

Call Order: 004 Proposal: T3930

ALT	Item	Description	Unit	Quantity
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.298
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	17.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	235.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	13.942
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.019
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	987.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.125
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (40901325201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (40901325203)	LS	1.000
Section 0003 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	19.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	16.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	50.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,117.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	410.000
	0710- 17- 1	PAINTED PAVEMENT MARKINGS, REMOVAL OF NON-CONFLICTING	SF	123.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (40901325201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	6,388.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,884.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,494.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.298
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	17.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	235.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	987.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.125
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	3,011.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	9.891
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	1.243
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	6.266

Call Order: 004 Proposal: T3930

ALT	Item	Description	Unit	Quantity
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	6.971
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.019
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	5,859.000
	0918-712-100	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 6"	GM	0.144
	0918-712-101	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 8"	GM	0.070
	0918-712-110	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 6"	GM	0.113
	0918-712-120	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, 10-30 SKIP 6"	GM	0.077
	0918-712-121	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, 3-9 DOTTED 6"	GM	0.003
	0918-712-130	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, BLACK, 10-30 SKIP 6"	GM	0.074
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,309.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,738.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	4.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0633- 4- 11	TELEPHONE CABLE, FURNISH & INSTALL	LF	14.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	510.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	67.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	105.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	24.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	10.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	2.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	1.000
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	9.000
	0650- 1- 36	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 4 SECTION, 1 WAY	AS	4.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	30.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	24.000

Call Order: 004 Proposal: T3930

ALT	Item	Description	Unit	Quantity
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	6.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	19.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	19.000
	0660- 1-600	LOOP DETECTOR INDUCTIVE, REMOVE- CABINET TO REMAIN	EA	40.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	26.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	30.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	24.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	6.000
	0670- 5-161	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA W/STANDARD LOCK, 1 PREEMPTION	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0670- 5-710	TRAFFIC CONTROLLER ASSEMBLY, MODIFY ONLY - NO COMPONENTS ADDED	AS	1.000
	0682- 1-163	ITS CCTV CAMERA, PRESSURIZED, IP, HIGH DEFINITION	EA	4.000
	0685- 1- 14	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION WITH CABINET	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2.000