

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250730	Call Order: 014	Proposal: T4726	District:04
Counties:	BROWARD			
Road Name:	UTOPIA DR			
Limits:	FROM RIVIERA BLVD TO SR 824 (PEMBROKE RD)			
Project(s):	44552415201(*)	Federal Aid No:	D425011B	
Total Roadway Length:	1.343 Miles	Contract Days:	87	
Total Bridge Length:	0.000 Miles	Letting Date:	07/30/25	
Total Proposal Length:	1.343 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	45 Days	
Proposal Budget Estimate:	\$1,729,484.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of, but are not limited to, MOT (standard, pedestrian LCD, PCMS), earthwork (excavation, embankment), environmental (sediment barrier, inlet protection), concrete (removal, sidewalk, driveways), asphalt (milling, resurfacing, misc), pavement markings (detectable, thermoplastic), signing (object marker, single-column), guardrail (general, removal, end treatment), lighting (conduit, pull/splice box, conductors, cable distribution system, pole complete-special), and tree work (protection, pruning, removal) for an asphalt path along Utopia Drive from Riviera Boulevard to State Road 824 (Pembroke Road) for 1.343 miles in the City of Miramar, Broward County.

Call Order: 014 Proposal: T4726

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44552415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44552415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,653.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,218.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,045.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	404.000
	0104- 10- 3	SEDIMENT BARRIER	LF	6,211.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	18.000
	0110- 1- 1	CLEARING & GRUBBING (44552415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	13.000
	0110- 21-	TREE PROTECTION BARRIER	LF	3,642.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	209.000
	0110- 23-	TREE REMOVAL	EA	23.000
	0120- 1-	REGULAR EXCAVATION	CY	3,719.100
	0120- 6-	EMBANKMENT	CY	153.100
	0160- 4-	TYPE B STABILIZATION	SY	7,267.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	4,435.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	365.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	103.700
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	87.000
	0527- 2-	DETECTABLE WARNINGS	SF	60.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	1,331.000

Call Order: 014 Proposal: T4726

ALT	Item	Description	Unit	Quantity
	0536- 73-	GUARDRAIL REMOVAL	LF	344.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	32.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	8,626.000
	0751- 38- 14	BENCH, F&I, STEEL	EA	24.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44552415201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	44.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	31.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	57.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	59.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	873.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	4,570.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	4,305.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	2.000
	0715-516-110	LIGHT POLE COMPLETE-SPECIAL DESIGN, F&I, POLE TOP MOUNT, ALUMINUM, 10'	EA	2.000