

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250611	Call Order: 001	Proposal: T1904	District:01
Counties:	SARASOTA			
Road Name:	SR 789			
Limits:	FROM E OF SUNSET DR TO BIRD KEY DR			
Project(s):	44592625201(*)	Federal Aid No:	D125041B	
Project(s):	44592625202	Federal Aid No:	D125041B	
Project(s):	44592625203	Federal Aid No:	D125041B	
Total Roadway Length:	0.575 Miles	Contract Days:	350	
Total Bridge Length:	0.625 Miles	Letting Date:	06/11/25	
Total Proposal Length:	1.200 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$10,784,270.00			

Please read the full advertisement

Description:

The work under this contract consists of roadway widening and reconstruction, milling and resurfacing, drainage, sidewalk, lighting, signalization, ITS and signing and pavement markings along SR 789 from East of Sunset Drive to Bird Key Drive in Sarasota County.

Call Order: 001 Proposal: T1904

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44592625201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44592625201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	30.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	264.000
	0102- 60-	WORK ZONE SIGN	ED	14,800.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	3,574.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	10,670.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	28,050.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	16,650.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	870.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,050.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	700.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	700.000
	0102-115-	TYPE III BARRICADE	ED	2,920.000
	0104- 10- 3	SEDIMENT BARRIER	LF	6,334.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	53.000
	0107- 1-	LITTER REMOVAL	AC	229.060
	0107- 2-	MOWING	AC	132.890
	0110- 1- 1	CLEARING & GRUBBING (44592625202)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44592625203)	LS	1.000

Call Order: 001 Proposal: T1904

ALT	Item	Description	Unit	Quantity
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	1.400
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	7,205.000
	0110- 73-	REMOVE EXISTING BULKHEAD	LF	337.000
	0120- 1-	REGULAR EXCAVATION	CY	2,238.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,419.000
	0120- 6-	EMBANKMENT	CY	3,270.000
	0160- 4-	TYPE B STABILIZATION	SY	5,172.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,391.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	3,471.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	23,748.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,053.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	177.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	8,708.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	2,385.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2.100
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	28.000
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	94.900
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	3,392.000
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	1.000
	0425- 1-203	INLETS, CURB, TYPE 9, J BOT, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	5.000
	0425- 1-359	INLETS, CURB, TYPE P-5, MODIFY	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	5.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	3.000
	0425- 1-459	INLETS, CURB, TYPE J-5, MODIFY	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	2.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 1-781	INLETS, MEDIAN BARRIER, TYPE 1, <=10'	EA	5.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	2.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	8.000
	0425- 2- 72	MANHOLES, J-7, >10'	EA	1.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	86.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	1,018.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	28.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	6.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	27.000
	0430-175-215	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 15"S/CD	LF	75.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	2.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY, 42" TYPE 1	LF	707.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	488.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	6,004.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	823.000

Call Order: 001 Proposal: T1904

ALT	Item	Description	Unit	Quantity
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	226.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	387.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	162.000
	0521- 1- 11	MEDIAN CONCRETE BARRIER, 38" HEIGHT	LF	576.000
	0521- 72- 43	SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER	LF	80.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	5,946.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	271.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	10.000
	0526- 1-101	PAVERS, ARCHITECTURAL, REMOVE EXISTING AND REINSTALL	SY	441.000
	0527- 2-	DETECTABLE WARNINGS	SF	722.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	88.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	10,045.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,500.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.683
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,500.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	925.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	5.027
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	69.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.785
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44592625201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44592625202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44592625203)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	37.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	5.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	10.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	38.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	4.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	3.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	4.000
	0700-141-802	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, RELOCATE - GROUND MOUNT	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	510.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	25.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44592625201)	LS	1.000

Call Order: 001 Proposal: T1904

ALT	Item	Description	Unit	Quantity
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	924.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	359.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	249.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.340
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	34.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	29.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	106.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.052
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	834.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	19.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	19.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	3.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.452
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.116
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.119
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.392
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.690
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.198
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.094
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.198
	0714- 10-	GREEN-COLORED PAVEMENT MARKINGS, BIKE LANE	SF	1,288.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	70.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,409.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	36.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	10.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	8,724.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 61-242	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 12' ARM LENGTH	EA	12.000
	0715- 61-321	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 10' ARM LENGTH	EA	1.000
	0715- 61-342	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 12' ARM LENGTH	EA	4.000
	0715- 68-000	LIGHT POLE COMPLETE, RELOCATE	EA	21.000

Call Order: 001 Proposal: T1904

ALT	Item	Description	Unit	Quantity
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	16.000
Section 0004 Signalization				
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	2.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	186.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,464.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	2.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	14.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	12.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	1.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	350.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	55.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	6.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	19.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	2.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	12.000
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	2.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	3.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	2.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	8.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	30.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	7.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	12.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	8.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	1.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	18.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	2.000
	0660- 4- 32	VEHICLE DETECTION SYSTEM- VIDEO, INSTALL ABOVE GROUND EQUIPMENT	EA	3.000

Call Order: 001 Proposal: T1904

ALT	Item	Description	Unit	Quantity
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	2.000
	0663- 1-123	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, CABINET ELECTRONICS	EA	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	10.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	12.000
	0670- 5-112	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 2 PREEMPTION	AS	2.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	3.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0684- 6- 40	WIRELESS COMMUNICATION DEVICE, RELOCATE	EA	1.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	2.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	2.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	10.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	13.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	8.000