

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250924	Call Order: 006	Proposal: T2A46	District:02
Counties:	DUVAL			
Road Name:	SR 212 (BEACH BLVD) AND SR 10 (ATLANTIC BLVD)			
Limits:	AT FOSTER DR AND LEON RD AND AT SPRING FOREST AVE AND CENTURY ST			
Project(s):	44721125201(*)	Federal Aid No: D225022B		
Total Roadway Length:	0.478 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	09/24/25	
Total Proposal Length:	4.081 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$1,290,306.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, drainage improvements, curb & gutter, highway signing, median modifications and other incidental construction on SR 212 (Beach Blvd) at Foster Dr & Leon Rd and SR 10 (Atlantic Blvd) at Spring Forest Ave & Century St in Duval County.

Call Order: 006 Proposal: T2A46

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44721125201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44721125201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,640.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,520.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	240.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	592.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	240.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	240.000
	0104- 10- 3	SEDIMENT BARRIER	LF	74.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	12.000
	0107- 1-	LITTER REMOVAL	AC	16.380
	0107- 2-	MOWING	AC	10.900
	0110- 1- 1	CLEARING & GRUBBING (44721125201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	351.000
	0120- 6-	EMBANKMENT	CY	266.200
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	10,802.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	854.300
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	1,406.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	391.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	448.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	34.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	628.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	442.000

Call Order: 006 Proposal: T2A46

ALT	Item	Description	Unit	Quantity
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.375
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.080
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	253.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	106.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.760
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	21.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.784
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	97.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.018
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44721125201)	LS	1.000
Section 0002 Signing				
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	11.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	17.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	442.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	50.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44721125201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.080
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	253.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	106.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.016
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	21.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	97.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	231.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.375
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.760
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.784
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.018
Section 0003 Signalization				
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	6.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	3.000