

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250528	Call Order: 021	Proposal: T7563	District:07
Counties:	HILLSBOROUGH			
Road Name:	SR 39 (JAMES L REDMAN PKWY)			
Limits:	AT TRAPNELL RD			
Project(s):	44539315201(*)	Federal Aid No:	D725012B	
Total Roadway Length:	0.530 Miles	Contract Days:	260	
Total Bridge Length:	0.000 Miles	Letting Date:	05/28/25	
Total Proposal Length:	0.530 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days	

Proposal Budget Estimate: \$9,169,250.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling asphalt pavement and resurfacing with concrete pavement on SR 39 at Trapnell Road in Hillsborough County.

Call Order: 021 Proposal: T7563

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44539315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44539315201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44539315201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44539315201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	21.200
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44539315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	400.000
	0102- 60-	WORK ZONE SIGN	ED	16,278.000
	0102- 61-	BUSINESS SIGN	EA	2.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	2,852.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	8,333.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	14,099.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	7,548.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	260.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,360.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	260.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	260.000
	0102-115-	TYPE III BARRICADE	ED	2,251.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,390.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	43.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	9.000
	0107- 1-	LITTER REMOVAL	AC	84.380

Call Order: 021 Proposal: T7563

ALT	Item	Description	Unit	Quantity
	0107- 2-	MOWING	AC	77.040
	0110- 1- 1	CLEARING & GRUBBING (44539315201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	407.000
	0120- 1-	REGULAR EXCAVATION	CY	2,797.000
	0120- 6-	EMBANKMENT	CY	322.100
	0160- 4-	TYPE B STABILIZATION	SY	9,531.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	158.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	9,810.000
	0327- 70- 39	MILLING EXISTING ASPHALT PAVEMENT, 9" AVG DEPTH	SY	142.000
	0327- 70- 46	MILLING EXISTING ASPHALT PAVEMENT, 12" AVG DEPTH	SY	19,865.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	4,141.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76 -22	TN	822.400
	0350- 3- 7	PLAIN CEMENT CONCRETE PAVEMENT, 9"	SY	24,776.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	35,941.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	24,776.000
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	5.000
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	5,162.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	420.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	357.000
	0520- 4-	CURB-CONCRETE PAVEMENT JOINT	LF	357.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	285.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	199.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	1,060.000
	0527- 2-	DETECTABLE WARNINGS	SF	190.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	16,281.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,456.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.709
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,007.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	302.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.436
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.142
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	48.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.686
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.042
	0710- 11-331	PAINTED PAVEMENT MARKINGS, STANDARD, BLACK, SKIP, 6"	GM	0.889
	0710- 11-341	PAINTED PAVEMENT MARKINGS, STANDARD, BLACK, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.306

Call Order: 021 Proposal: T7563

ALT	Item	Description	Unit	Quantity
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44539315201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	8.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	6.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	2.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	521.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	135.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44539315201)	LS	1.000
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.335
	0711- 14-241	THERMOPLASTIC, PREFORMED, YELLOW, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.063
	0711- 14-341	THERMOPLASTIC, PREFORMED, BLACK, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.330
	0711- 14-526	THERMOPLASTIC, PREFORMED, 24" WHITE WITH 4" BLACK CONTRAST FOR CROSSWALK ON CONCRETE PAVEMENT, 32"	LF	738.000
	0711- 14-527	THERMOPLASTIC, PREFORMED, 24" WHITE WITH 4" BLACK CONTRAST FOR STOP LINE ON CONCRETE PAVEMENT, 32"	LF	132.000
	0711- 14-528	THERMOPLASTIC, PREFORMED, 12" WHITE WITH 4" BLACK CONTRAST FOR CROSSWALK ON CONCRETE PAVEMENT, 20"	LF	792.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	2.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	20.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.576
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.576
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.576
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.321
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.844
	0713-103-121	PERMANENT TAPE, WHITE, SOLID W/CONTRAST, 6" PRIMARY LINE WIDTH, FOR CONCRETE SURFACES	GM	0.454
	0713-103-141	PERMANENT TAPE, WHITE, 6-10 SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.047
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.867
	0713-103-241	PERMANENT TAPE, YELLOW, 6-10 DOTTED EXTENSION, 6" WIDE, FOR CONCRETE SURFACES	GM	0.159
	0713-103-341	PERMANENT TAPE, BLACK, 6-10 DOTTED EXTENSION, 6" FOR CONCRETE SURFACES	GM	0.042

Call Order: 021 Proposal: T7563

ALT	Item	Description	Unit	Quantity
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.871
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	396.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	145.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,905.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	19.000
	0715- 68-000	LIGHT POLE COMPLETE, RELOCATE	EA	3.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	3.000
Section 0004 Signalization				
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	2.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	2.000
	0650- 1- 70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	4.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	8.000
	0660- 1-600	LOOP DETECTOR INDUCTIVE, REMOVE- CABINET TO REMAIN	EA	8.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	2.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	2.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	1.000
	0685- 1- 30	UNINTERRUPTIBLE POWER SUPPLY, INSTALL - EQUIPMENT FURNISHED BY OTHERS	EA	1.000
	0685- 1- 60	UNINTERRUPTIBLE POWER SUPPLY, REMOVE- POLE/CABINET REMAINS	EA	1.000