

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250611	Call Order: 002	Proposal: T3852	District:03
Counties:	FRANKLIN			
Road Name:	SR 30 (US 98 / US 319)			
Limits:	FROM S OF FRANKLIN ST TO CARRABELLE RIVER BRIDGE			
Project(s):	44576115201(*)	Federal Aid No:	D322069B	
Project(s):	44576115202	Federal Aid No:	D322069B	
Project(s):	44576115203	Federal Aid No:	D322069B	
Total Roadway Length:	15.247 Miles	Contract Days:	610	
Total Bridge Length:	0.034 Miles	Letting Date:	06/11/25	
Total Proposal Length:	15.281 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$17,294,727.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of (FPID: 445761-1-52-01) Milling and Resurfacing of SR 30 (US 98/319) from S. Franklin Street to the Carrabelle River Bridge. Other improvements include sections of roadway reconstruction, sidewalk construction, paved shoulder construction, guardrail improvements, cross slope correction, and resurfacing of the shared use path near Carrabelle Beach Park. This project will also receive upgrades to signing and pavement markings along SR 30 (US 98/319) and on the Carrabelle River Bridge. (FPID: 445761-1-52-02) consists of Signing and Pavement Marking Safety Improvements within the project limits. (FPID: 445761-1-52-03) consists of replacing two box culverts with bridge culverts: BR 490038 (MP 170112) and BR 490039 (MP 18.005) and will require the use of temporary signals as part of the staged construction. Other improvements include the addition of Articulated Concrete Block (ACB) along the project limits where none currently exist and multiple cross drain replacements. All work is to be done in Franklin County.

Call Order: 002 Proposal: T3852

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0145- 2-	GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	SY	414.000
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	420.300
	0415- 10- 3	FIBER REINFORCED POLYMER BARS, #3 BAR	LF	1,197.000
	0415- 10- 4	FIBER REINFORCED POLYMER BARS, #4 BAR	LF	37,674.000
	0415- 10- 5	FIBER REINFORCED POLYMER BARS, #5 BAR	LF	18,077.000
	0415- 10- 6	FIBER REINFORCED POLYMER BARS, #6 BAR	LF	6,038.000
	0415- 10- 7	FIBER REINFORCED POLYMER BARS, #7 BAR	LF	6,143.000
	0415- 10- 8	FIBER REINFORCED POLYMER BARS, #8 BAR	LF	5,576.000
	0415- 10- 10	FIBER REINFORCED POLYMER BARS, #10 BAR	LF	28,142.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	4,838.000
	0530- 74-	BEDDING STONE	TN	537.900
	0548- 13-	RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	SF	1,014.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44576115201)	LS	1.000
	0101- 1-	MOBILIZATION (44576115202)	LS	1.000
	0101- 1-	MOBILIZATION (44576115203)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44576115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44576115202)	LS	1.000

Call Order: 002 Proposal: T3852

ALT	Item	Description	Unit	Quantity
	0102- 1-	MAINTENANCE OF TRAFFIC (44576115203)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44576115201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44576115203)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44576115203)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	1,040.900
	0102- 60-	WORK ZONE SIGN	ED	45,558.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	70.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	684.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	1,836.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	64,851.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	936.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	10,836.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,282.000
	0102-115-	TYPE III BARRICADE	ED	1,030.000
	0102-120-	TEMPORARY TRAFFIC SIGNALS FOR LANE CLOSURES ON TWO-LANE,TWO-WAY ROADWAYS	ED	236.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	1,456.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,411.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	117.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	13.000
	0107- 1-	LITTER REMOVAL	AC	2,022.320
	0107- 2-	MOWING	AC	1,363.140
	0110- 1- 1	CLEARING & GRUBBING (44576115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44576115203)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	532.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	6.000
	0120- 1-	REGULAR EXCAVATION	CY	450.300
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	4,819.900
	0120- 4-	SUBSOIL EXCAVATION	CY	245.500
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,391.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	364.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	6,994.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	63.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	228,865.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	736.000
	0327- 70- 13	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH	SY	1,216.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	20,369.700
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-9.5, PG 76-22	TN	23,235.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	318.200
	0425- 1-335	INLETS, CURB, TYPE P-3, PARTIAL	EA	1.000
	0425- 1-529	INLETS, DT BOT, TYPE C, MODIFY	EA	2.000

Call Order: 002 Proposal: T3852

ALT	Item	Description	Unit	Quantity
	0425- 1-531	INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'	EA	1.000
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	6.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	9.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	30.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	108.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	146.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	201.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	623.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	258.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	67.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	25.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	5.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	11.000
	0430-530-100	STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 0 DEGREES, ROUND	EA	6.000
	0430-530-102	STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 0 DEGREES, ELLIPTICAL	EA	1.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-602-125	U-ENDWALL, WITH GRATE,INDEX 260/430-010, 1:4 SLOPE, 18"	EA	1.000
	0430-602-129	U-ENDWALL, WITH GRATE, INDEX 260/430-010, 1:4 SLOPE, 24"	EA	5.000
	0430-602-133	U-ENDWALL, WITH GRATE, INDEX 260/430-010, 1:4 SLOPE, 30"	EA	2.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	2.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	3.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	30.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	12.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	4.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	181.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	135.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	539.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	179.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	3.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	103.000
	0527- 2-	DETECTABLE WARNINGS	SF	304.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	2,224.800
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	43.200
	0530- 4- 9	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 9" (44576115203)	SY	3,327.000
	0530- 74-	BEDDING STONE	TN	1,823.700
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	540.000

Call Order: 002 Proposal: T3852

ALT	Item	Description	Unit	Quantity
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	308.000
	0536- 8-111	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-2	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,462.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	8.000
	0538- 1-	GUARDRAIL RESET	LF	420.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	40,372.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	1,022.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	31.596
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.046
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	979.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	421.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	712.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.101
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	7.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	21.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	21.105
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	442.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	6.789
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.011
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44576115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44576115202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44576115203)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	30.994
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	69.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	8.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	5.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	69.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	7.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	24.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	9,464.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44576115201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	979.000

Call Order: 002 Proposal: T3852

ALT	Item	Description	Unit	Quantity
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	421.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	664.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.101
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	18.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	442.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.011
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	50.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	3.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	3.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	30.356
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.046
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	20.341
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	6.735
	0918-712-100	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, WHITE, SOLID 6"	GM	0.746
	0918-712-110	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, SOLID 6"	GM	0.720
	0918-712-115	INTEGRATED MULTI-POLYMER PAVEMENT MARKINGS, YELLOW, 10-30 SKIP 6"	GM	0.012