

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT260325 Call Order: 024 Proposal: T4753 District:04

Counties: BROWARD

Road Name: SR 814 (W ATLANTIC BLVD)

Limits: FROM W OF LAKESIDE DR TO VISTA VERDE

Project(s): 45108215201(*) Federal Aid No: D426011B

Total Roadway Length:	0.549 Miles	Contract Days:	55
Total Bridge Length:	0.000 Miles	Letting Date:	03/25/26
Total Proposal Length:	0.549 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60

Proposal Budget Estimate: \$318,476.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of , but are not limited to, MOT (standard, traffic control officer, ped LCD, arrow board, PCMS, signalization, traffic detection), concrete (remove, sidewalk, driveways), conduit, pull/splice box, lighting (prestressed pole, prestressed pole remove, conductors, luminaire, pole complete, cable distribution), signalization (cable, span wire, controller, illuminated sign, illuminated sign remove), electrical service (remove, power, wire, disconnect, load center, load center remove), along State Road 814 (W. Atlantic Boulevard) from west of Lakeside Drive to Vista Verde for 0.549 miles in the Cities of Margate and Coconut Creek, Broward County.

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <https://www.fdot.gov/equalopportunity/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at <https://www.fdot.gov/equalopportunity/bdi.shtm>

Prequalification per Rule 14-22 is not required. Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at <https://www.fdot.gov/equalopportunity/bdi.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year. Send a completed and notarized affidavit as an attachment to SmallBusiness@dot.state.fl.us

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the projects major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the AASHTOWare Project Bids application.

BDI Reference Sheet may be downloaded from CPP Online Ordering.

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashiers Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

Call Order: 024 Proposal: T4753

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45108215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45108215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	16.000
	0102- 60-	WORK ZONE SIGN	ED	2,860.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,440.000

Call Order: 024 Proposal: T4753

ALT	Item	Description	Unit	Quantity
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,320.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	55.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	138.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	55.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	55.000
	0107- 1-	LITTER REMOVAL	AC	2.770
	0107- 2-	MOWING	AC	1.260
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	44.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	44.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45108215201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	560.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	12.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	15.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	115.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,321.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	1,220.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	14.000
	0715- 61-442	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 12' ARM LENGTH	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	15.000
Section 0003 Signalization				
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0634- 4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	1.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	1.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	2.000