

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT260610 Call Order: 004 Proposal: T3952 District:03
 Counties: WAKULLA
 Road Name: CR 372 (SURF RD)
 Limits: OVER OTTER CREEK RISE, BRIDGE NO 59069
 Project(s): 44295115201(*) Federal Aid No: D325030B
 Project(s): 44295115601 Federal Aid No: N/A
 Total Roadway Length: 0.159 Miles Contract Days: 490
 Total Bridge Length: 0.017 Miles Letting Date: 06/10/26
 Total Proposal Length: 0.176 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 120 Days Flexible
 Proposal Budget Estimate: \$10,494,586.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of replacement of the structurally deficient bridge along CR 372 (Surf Road) over Otter Creek Rise Bridge No. 594049 with the new Bridge No. 594069 in Wakulla County. Also included are signing and pavement markings and a temporary on-site diversion. FPID 442951-1-56-01 includes UWHC water main replacement.

Call Order: 004 Proposal: T3952

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44295115201)	LS	1.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	129.400
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	120.200
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	369.000
	0400- 4- 47	CONCRETE CLASS IV, CAST IN PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	CY	136.500
	0400- 7- 1	BRIDGE DECK GROOVING	SY	397.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	14.200
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	591.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	25,456.000
	0415- 10- 4	FIBER REINFORCED POLYMER BARS, #4 BAR	LF	6,110.000
	0415- 10- 5	FIBER REINFORCED POLYMER BARS, #5 BAR	LF	34,317.000
	0415- 10- 6	FIBER REINFORCED POLYMER BARS, #6 BAR	LF	38,185.000
	0415- 10- 7	FIBER REINFORCED POLYMER BARS, #7 BAR	LF	9,928.000
	0415- 10- 9	FIBER REINFORCED POLYMER BARS, #9 BAR	LF	3,003.000
	0450- 8- 52	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 12" CFRP/SS, WIDTH 52-54"	LF	345.000
	0450- 8- 53	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 12" CFRP/SS, WIDTH 55-57"	LF	691.000
	0455- 15- 16	PREFORMED PILE HOLES, 36" TO 43" DRILL/PUNCH SIZE	LF	1,331.000
	0455- 15- 26	PREFORMED PILE HOLES CASING, 36" TO 43" DRILL/PUNCH SIZE	LF	1,403.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	68.000
	0455- 34- 25	PRESTRESSED CONCRETE PILING, 24" SQ W/FRP OR STAINLESS STEEL STRAND AND REINFORCING	LF	3,780.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	4,789.000

Call Order: 004 Proposal: T3952

ALT	Item	Description	Unit	Quantity
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	68.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	19.000
	0455-143- 25	TEST PILES-PRESTRESSED CONCRETE, 24" SQ W/ FRP OR STAINLESS STEEL STRAND AND REINFORCING	LF	1,465.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	288.000
	0515- 4- 2	BULLET RAIL, DOUBLE RAIL	LF	306.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	150.000
	0521- 5-101	CONCRETE TRAFFIC RAILING- BRIDGE, 36" FRP-RC SINGLE SLOPE	LF	248.000
	0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	306.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	142.500
	0530- 3- 5	RIPRAP- RUBBLE, COASTAL SHORE- LARGE BOULDERS	TN	3,013.600
	0530- 74-	BEDDING STONE	TN	931.500
	0548- 13-	RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	SF	1,647.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	1,555.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	12.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44295115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44295115201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44295115201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44295115201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	13.900
	0102- 60-	WORK ZONE SIGN	ED	5,010.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	120.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	2,413.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	2,088.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,794.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	255,050.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	8.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,008.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.056
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.056
	0104- 10- 3	SEDIMENT BARRIER	LF	1,890.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	492.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	530.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44295115201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44295115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44295115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	325.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	14.000
	0120- 1-	REGULAR EXCAVATION	CY	2,420.400

Call Order: 004 Proposal: T3952

ALT	Item	Description	Unit	Quantity
	0120- 4-	SUBSOIL EXCAVATION	CY	756.700
	0120- 6-	EMBANKMENT	CY	7,150.700
	0121- 70-	FLOWABLE FILL	CY	7.000
	0141- 70-	SETTLEMENT PLATE ASSEMBLY	AS	9.000
	0145- 3-	GEOSYNTHETIC REINFORCED EMBANKMENT	SY	1,066.000
	0160- 4-	TYPE B STABILIZATION	SY	5,106.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,084.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,077.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,252.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	348.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,017.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	288.200
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	261.600
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	56.100
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	19.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	61.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	1.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	121.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	91.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	11.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	35.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	1.100
	0530- 74-	BEDDING STONE	TN	0.800
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	259.000
	0536- 8-111	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-001, APPROACH TL-2	EA	2.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-001, TRAILING	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	610.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	8,571.000
	0571- 1- 12	PLASTIC EROSION MAT, TRM, TYPE 2	SY	668.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,950.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.864
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.870
Section 0003 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	6.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	7.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0705- 10- 4	OBJECT MARKER, TYPE 4	EA	3.000

Call Order: 004 Proposal: T3952

ALT	Item	Description	Unit	Quantity
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	58.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44295115201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.472
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.315
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.078
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.036
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.036
Section 0004 Utilities				
	0104- 10- 3	SEDIMENT BARRIER	LF	284.000
	1050- 42-206	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	14.000
	1050- 42-210	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 10"	LF	657.000
	1055- 51-110	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 10"	EA	4.000
	1055- 51-210	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 10"	EA	2.000
	1080- 23-110	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 10"	EA	1.000
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	2.000
	1080- 24-110	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 10"	EA	2.000
	1644-113- 08	FIRE HYDRANT, F&I, STANDARD, 2 HOSE, 1PUMPER, 6"	EA	2.000