

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251203	Call Order: 008	Proposal: T3993	District:03
Counties:	ESCAMBIA			
Road Name:	SR 97 (ATMORE HWY)			
Limits:	FROM SR 95 (US 29) TO ALABAMA STATE LINE			
Project(s):	45082115201(*)	Federal Aid No:	D325058B	
Project(s):	45082115202	Federal Aid No:	D325058B	
Total Roadway Length:	21.991 Miles	Contract Days:	567	
Total Bridge Length:	0.003 Miles	Letting Date:	12/03/25	
Total Proposal Length:	22.021 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$15,189,892.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of FPID 450821-1-52-01, SR 97 (Atmore Highway) from SR 95 (US 29) to the Alabama State Line in Escambia County. Existing travel lanes, auxiliary lanes, and paved shoulders will be resurfaced. Additionally, the project includes necessary signing and pavement marking upgrades for improved safety and function. The improvements under FPID 450821-1-52-02 consist of storm sewer improvements at the SR 95 (US 29) intersection. This construction will improve drainage and alleviate historic flooding by installing an additional 3'x8' box culvert across the southern leg of the intersection and two (2) additional 24" cross drains on the norther leg of the intersection.

Call Order: 008 Proposal: T3993

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45082115201)	LS	1.000
	0101- 1-	MOBILIZATION (45082115202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45082115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45082115202)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (45082115201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (45082115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,375.000
	0102- 60-	WORK ZONE SIGN	ED	40,294.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	312.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	504.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	242,075.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	360.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	3,484.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	567.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	567.000
	0102-115-	TYPE III BARRICADE	ED	540.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	447.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.630
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.574
	0104- 10- 3	SEDIMENT BARRIER	LF	18.000

Call Order: 008 Proposal: T3993

ALT	Item	Description	Unit	Quantity
	0104- 18-	INLET PROTECTION SYSTEM	EA	11.000
	0107- 1-	LITTER REMOVAL	AC	3,351.240
	0107- 2-	MOWING	AC	3,351.240
	0110- 1- 1	CLEARING & GRUBBING (45082115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45082115202)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	108.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	42.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (45082115202)	LS	1.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	4,078.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	441.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	1,097.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	41.400
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	315,073.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	4,895.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	12,831.000
	0327- 70- 13	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH	SY	4,289.000
	0327- 70- 16	MILLING EXISTING ASPHALT PAVEMENT, 1/2" AVG DEPTH	SY	133,804.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	26,215.600
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,331.100
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	514.800
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	37,090.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	714.400
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	224.700
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	41,675.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	16.000
	0430-174-136	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	LF	134.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	288.000
	0430-524-200	STRAIGHT CONCRETE ENDWALLS, 24", DOUBLE, 0 DEGREES, ROUND	EA	2.000
	0430-984-120	MITERED END SECTION, OPTIONAL ROUND, 8" SD	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	1.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	4.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	112.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	28.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	23.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	132.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	14.800
	0530- 74-	BEDDING STONE	TN	15.900
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	72,387.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	2,876.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	2.000

Call Order: 008 Proposal: T3993

ALT	Item	Description	Unit	Quantity
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	21,193.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	90.985
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.101
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	380.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	969.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,554.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.394
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.846
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	41.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	98.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	88.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	82.342
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	818.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	50.676
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.672
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45082115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45082115202)	LS	1.000
Section 0002 Signing				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	4.000
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	61.103
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	47.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	38.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	6,612.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	76.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45082115201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45082115202)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	190.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	818.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	897.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.537
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	46.000

Call Order: 008 Proposal: T3993

ALT	Item	Description	Unit	Quantity
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	44.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	409.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.287
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	134.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	13.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	13.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	1.057
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.029
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.697
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.427
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	44.631
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.072
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	26.837
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	12.669
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.061
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.061
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	3.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	8.000