

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 006	Proposal: T2A83	District:02
Counties:	DUVAL			
Road Name:	SR 13 (HENDRICKS AVE)			
Limits:	FROM SAN MARCO BLVD TO PRUDENTIAL DR			
Project(s):	20969755201(*)	Federal Aid No:	D226037B	
Total Roadway Length:	0.881 Miles	Contract Days:	250	
Total Bridge Length:	0.000 Miles	Letting Date:	10/28/26	
Total Proposal Length:	0.881 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$2,409,934.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, base work, drainage improvements, curb & gutters, traffic signals, highway signing, sidewalks/bicycle path, and other incidental construction on SR 13 (Hendricks Ave) in Duval County from San Marco Blvd to Prudential Drive.

Call Order: 006 Proposal: T2A83

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (20969755201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (20969755201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	212.000
	0102- 60-	WORK ZONE SIGN	ED	10,795.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	156.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	23,800.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,551.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	656.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	818.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,500.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,500.000
	0102-115-	TYPE III BARRICADE	ED	565.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	34.000
	0107- 1-	LITTER REMOVAL	AC	25.220
	0107- 2-	MOWING	AC	0.410
	0110- 1- 1	CLEARING & GRUBBING (20969755201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	49.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	30.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	16,112.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	7,722.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	1,111.900
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-9.5, PG 76-22	TN	1,638.600

Call Order: 006 Proposal: T2A83

ALT	Item	Description	Unit	Quantity
	0425- 1-205	INLETS, CURB, TYPE 9, PARTIAL	EA	1.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	1.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	22.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	55.000
	0425- 6-	VALVE BOXES, ADJUST	EA	58.000
	0425-100- 44	SPECIAL DRAINAGE STRUCTURE, UTILITY CONFLICT MANHOLE, TYPE P-8	EA	1.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	64.000
	0431- 1-112	PIPE LINER, CURED IN PLACE, 12"	LF	49.000
	0431- 1-115	PIPE LINER, CURED IN PLACE, 15"	LF	210.000
	0431- 1-142	PIPE LINER, CURED IN PLACE, 42"	LF	47.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	47.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	16.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	22.000
	0527- 2-	DETECTABLE WARNINGS	SF	78.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.400
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,295.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.467
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.955
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20969755201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	52.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	32.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	5.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	656.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (20969755201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,481.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	476.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	692.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.467
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	53.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	506.000

Call Order: 006 Proposal: T2A83

ALT	Item	Description	Unit	Quantity
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.067
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,766.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	52.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	35.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.471
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.795
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.300
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	100.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	6.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	7.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	7.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	8.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	5.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	3.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	1.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	34.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	39.000
	0665- 1- 50	PEDESTRIAN DETECTOR, ADJUST/MODIFY ON EXISTING POLE	EA	19.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	25.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	1.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	12.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	13.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	1.000