

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261202	Call Order: 006	Proposal: T2A71	District:02
Counties:	LEVY			
Road Name:	SR 320 (NW 115TH ST)			
Limits:	FROM MANATEE SPRINGS STATE PARK TO SR 55 (US 19)			
Project(s):	21029235201(*)	Federal Aid No:	D226057B	
Total Roadway Length:	5.743 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	12/02/26	
Total Proposal Length:	5.743 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$3,355,051.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, base work, shoulder treatment, drainage improvements, highway signing, and other incidental construction on SR 320/NW 115th Street in Levy County from Manatee Springs State Park to SR 55 (US 19).

Call Order: 006 Proposal: T2A71

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (21029235201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21029235201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	14,850.000
	0102- 61-	BUSINESS SIGN	EA	5.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	9,712.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	902.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	628.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	150.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	150.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	1,080.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,002.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	6.000
	0107- 1-	LITTER REMOVAL	AC	201.870
	0107- 2-	MOWING	AC	153.150
	0110- 1- 1	CLEARING & GRUBBING (21029235201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	10.000
	0160- 4-	TYPE B STABILIZATION	SY	808.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	4,285.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	75,763.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	47,920.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	12,354.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	2.000

Call Order: 006 Proposal: T2A71

ALT	Item	Description	Unit	Quantity
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	30,780.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	2,872.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	20.126
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	81.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	738.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.753
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	115.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	115.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.885
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	84.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	4.667
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21029235201)	LS	1.000
Section 0002 Signing				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	4.000
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	13.455
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	9.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	902.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21029235201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	81.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	738.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.753
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	84.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	62.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	115.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	115.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	20.126
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.885
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	4.667