

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT260520 Call Order: 013 Proposal: T7587 District:07
 Counties: HILLSBOROUGH
 Road Name: SR 597 (N DALE MABRY HWY)
 Limits: FROM N OF W SOUTH AVE TO N OF W WATERS AVE
 Project(s): 44797315201(*) Federal Aid No: D726004B
 Project(s): 44797315601 Federal Aid No: N/A
 Total Roadway Length: 3.126 Miles Contract Days: 225
 Total Bridge Length: 0.042 Miles Letting Date: 05/20/26
 Total Proposal Length: 3.168 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 120 Days
 Proposal Budget Estimate: \$9,211,667.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, drainage improvements, curb and gutter, signage, pavement markings, and signalization on SR 597/ N Dale Mabry Hwy. from North of W. South Ave. to North of W. Waters Ave. in Hillsborough County.

Call Order: 013 Proposal: T7587

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	76.600
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	21,006.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44797315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44797315201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44797315201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	201.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,512.000
	0102- 60-	WORK ZONE SIGN	ED	20,668.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,404.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	264.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	41,919.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	17,473.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	496.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	790.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	705.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	675.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	225.000
	0102-115-	TYPE III BARRICADE	ED	990.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	92.000
	0107- 1-	LITTER REMOVAL	AC	268.320
	0107- 2-	MOWING	AC	166.520

Call Order: 013 Proposal: T7587

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (44797315201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	842.000
	0120- 1-	REGULAR EXCAVATION	CY	1,710.800
	0120- 6-	EMBANKMENT	CY	1,747.200
	0160- 4-	TYPE B STABILIZATION	SY	350.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	350.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	87,056.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	8,415.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	46,873.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	10,615.900
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	11,460.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	37.200
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	89.000
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	6.200
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	1,241.000
	0425- 1-315	INLETS, CURB TYPE P-1, PARTIAL	EA	2.000
	0425- 1-325	INLETS, CURB, TYPE P-2, PARTIAL	EA	1.000
	0425- 1-411	INLETS, CURB TYPE J-1, <10'	EA	2.000
	0425- 1-421	INLETS, CURB, TYPE J-2, <10'	EA	1.000
	0425- 1-441	INLETS, CURB, TYPE J-4, <10'	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	17.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	8.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	44.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	16.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	8.000
	0430-185-148	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 48", STORM AND CROSS DRAIN	LF	108.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	37.900
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	105.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	494.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	46.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	1.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	513.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	293.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	27.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT,NON REINFORCED, 4"	SY	113.000
	0527- 2-	DETECTABLE WARNINGS	SF	59.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	454.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	141.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	200.000
	0536- 73-	GUARDRAIL REMOVAL	LF	494.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000

Call Order: 013 Proposal: T7587

ALT	Item	Description	Unit	Quantity
	0536- 85- 27	GUARDRAIL END TREATMENT- DOUBLE FACE APPROACH TERMINAL	EA	1.000
	0538- 1-	GUARDRAIL RESET	LF	200.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,468.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	94.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	189.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	12.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	12.000
	0695- 7-162	TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	EA	2.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,703.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	7.482
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.744
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	5,050.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,763.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	4,390.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	7.679
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.157
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.411
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	73.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	201.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.241
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	63.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.353
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.387
	0906-173-200	TWO COMPONENT POLYURETHANE INJECTION	LB	14,250.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44797315201)	LS	1.000
Section 0003 Signing				
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	1.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	118.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	22.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	3.000

Call Order: 013 Proposal: T7587

ALT	Item	Description	Unit	Quantity
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	113.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	9.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	2.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	3.000
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	2.000
	0700- 3-106	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 101-200 SF	EA	1.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	1.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	9.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	2.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	3.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	2.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	2.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	2.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	18.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	28.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	27.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,703.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	148.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44797315201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	5,050.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,763.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	849.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.411
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	143.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	63.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.387
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	3,541.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	58.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	58.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	7.482
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.744
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	7.679
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.157
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.241

Call Order: 013 Proposal: T7587

ALT	Item	Description	Unit	Quantity
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.353
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.085
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.170
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.085
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.170
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	119.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	317.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	80.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	2.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	225.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	9.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	26.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	2.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	4.000
	0660- 4- 51	VEHICLE DETECTION SYSTEM- VIDEO, ADJUST/MODIFY CABINET EQUIPMENT	EA	1.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	3.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	1.000
Section 0005 Utilities				
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (44797315601)	LS	1.000
	1050- 16-002	UTILITY PIPE,REMOVE & DISPOSE, 2-4.9"	LF	56.000
	1050- 31-204	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 4"	LF	56.000
	1050- 42-204	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 4"	LF	84.000
	1080- 29-104	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 4"	EA	2.000