

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260128	Call Order: 016	Proposal: T7580	District:07
Counties:	HILLSBOROUGH			
Road Name:	SR 574 (W REYNOLDS ST)			
Limits:	FROM E OF SR 39 TO W OF US 92			
Project(s):	45411815201(*)	Federal Aid No:	D725043B	
Project(s):	45411815601	Federal Aid No:	N/A	
Total Roadway Length:	0.019 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	01/28/26	
Total Proposal Length:	0.019 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$779,316.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of replacement of the box culvert on SR 574 / W Reynolds Street from East of SR 39 to West of US 92. Work also consists of Utility Work by Highway Contractor for gravity sanitary sewer replacement for the City of Plant City facilities. The project is located in Hillsborough County.

Call Order: 016 Proposal: T7580

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45411815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45411815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	9,660.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,324.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,400.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	870.000
	0102-115-	TYPE III BARRICADE	ED	800.000
	0104- 10- 3	SEDIMENT BARRIER	LF	257.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	30.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	42.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0107- 1-	LITTER REMOVAL	AC	0.220
	0107- 2-	MOWING	AC	0.190
	0110- 1- 1	CLEARING & GRUBBING (45411815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	93.000
	0110- 21-	TREE PROTECTION BARRIER	LF	27.000
	0120- 1-	REGULAR EXCAVATION	CY	152.000
	0120- 6-	EMBANKMENT	CY	3.000
	0160- 4-	TYPE B STABILIZATION	SY	194.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	179.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	544.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	29.500

Call Order: 016 Proposal: T7580

ALT	Item	Description	Unit	Quantity
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	58.300
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	115.700
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	11,311.000
	0425- 1-481	INLETS, CURB, TYPE 8, <10'	EA	4.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	48.000
	0515- 4- 1	BULLET RAIL, SINGLE RAIL	LF	91.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	143.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	91.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	46.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	97.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	50.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	9.600
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	16.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.025
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.025
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45411815201)	LS	1.000
Section 0002 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	16.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45411815201)	LS	1.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.109
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.109
Section 0003 Utilities				
	0400-153-	NON SHRINK GROUT, F&I, MISCELLANEOUS- STRUCTURES REHAB	CF	37.000
	0530- 74-	BEDDING STONE	TN	3.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	33.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (45411815601)	LS	1.000
	1050- 16-003	UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	LF	60.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	80.000
	1050- 18-003	UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 5- 7.9"	LF	188.000
	1050- 31-208	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 8"	LF	50.000
	1060- 11-211	UTILITY STRUCTURE, BELOW GROUND, F&I, WATER/SEWER, 0 - 80 FT3, 0 - 6'	EA	2.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	2.000
	1060- 31- 1	UTILITY STRUCTURE, FURNISH AND INSTALL- REPLACE EXISTING RIM	EA	2.000
	1060- 31- 2	UTILITY STRUCTURE, FURNISH AND INSTALL- REPLACE EXISTING COVER	EA	2.000
	1080- 21-600	UTILITY FIXTURE, VALVE/METER BOX, REMOVE	EA	4.000