

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260128	Call Order: 005	Proposal: T3929	District:03
Counties:	CALHOUN			
Road Name:	CR 274			
Limits:	OVER TENMILE CREEK BRIDGE NO. 470035			
Project(s):	44544815201(*)	Federal Aid No:	D325032B	
Total Roadway Length:	0.357 Miles	Contract Days:	730	
Total Bridge Length:	0.043 Miles	Letting Date:	01/28/26	
Total Proposal Length:	0.400 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$9,095,837.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of CR 274 over Tenmile Creek Bridge No. 470035 bridge replacement. Other work will include milling and resurfacing, guardrail, signing and pavement marking, and utility adjustments. All work is to be done in Calhoun County.

Call Order: 005 Proposal: T3929

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44544815201)	LS	1.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	98.700
	0400- 2- 47	CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	CY	276.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	135.700
	0400- 7- 1	BRIDGE DECK GROOVING	SY	1,085.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	1,085.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	22.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	64,026.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	17,445.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	18,896.000
	0415- 10- 5	FIBER REINFORCED POLYMER BARS, #5 BAR	LF	1,740.000
	0450- 8- 13	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 12" CARBON STEEL, WIDTH 55-57"	LF	2,099.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	35.000
	0455- 35- 22	STEEL PILING, 24" DIA. PIPE	LF	2,278.000
	0455-115-	PILE REDRIVE	EA	14.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	35.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	7.000
	0455-144- 22	TEST PILES - STEEL, 24" DIA PIPE	LF	677.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	83.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	600.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	29.600
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,105.400

Call Order: 005 Proposal: T3929

ALT	Item	Description	Unit	Quantity
	0530- 74-	BEDDING STONE	TN	411.600
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44544815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44544815201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44544815201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44544815201)	LS	1.000
	0102- 2-400	SPECIAL DETOUR- TEMPORARY BRIDGE (44544815201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	2.600
	0102- 60-	WORK ZONE SIGN	ED	18,390.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	450.000
	0102- 73-	TEMPORARY GUARDRAIL	LF	480.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	53,102.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,488.000
	0102-115-	TYPE III BARRICADE	ED	4,640.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	860.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	600.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,678.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	26.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44544815201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44544815201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44544815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	115.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	1.000
	0120- 1-	REGULAR EXCAVATION	CY	1,083.800
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,837.800
	0160- 4-	TYPE B STABILIZATION	SY	3,679.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	380.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	2,624.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,956.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	194.500
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	490.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	16.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	3.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	4.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	113.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	4.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	446.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	95.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	449.000

Call Order: 005 Proposal: T3929

ALT	Item	Description	Unit	Quantity
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	859.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,421.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	840.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.760
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	14.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.760
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	0.997
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	5.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	102.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44544815201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	41.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.713
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.540
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.141
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.091
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.091