

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT260128 Call Order: 011 Proposal: T5874 District:05
 Counties: ORANGE
 Road Name: SR 426 (FAIRBANKS AVE / ALOMA AVE)
 Limits: FROM S PARK AVE TO N LAKEMONT AVE AND FROM EASTBROOK BLVD TO UNNAMED CANAL
 NEAR FORSYTH RD

Project(s): 45077515201 Federal Aid No: N/A
 Project(s): 45128225201(*) Federal Aid No: D525007B
 Project(s): 45128225202 Federal Aid No: N/A

Total Roadway Length: 1.962 Miles Contract Days: 360
 Total Bridge Length: 0.010 Miles Letting Date: 01/28/26
 Total Proposal Length: 1.972 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 120 Days

Proposal Budget Estimate: \$8,684,298.00

Please read the full advertisement

Description:

The improvements under this Contract consist of raised pedestrian crossings, pedestrian hybrid beacons, raised intersections, milling and resurfacing, curb and gutter, sidewalk, drainage improvements, signal improvements, lighting, and signing and pavement markings on northbound and southbound SR 426 from S Park Ave. to N. Lakemont Ave. The approximate length of the project is 1.683 miles, and it is in Orange County.

The improvements under this Contract consist of milling and resurfacing, curb ramps (ADA), and pavement markings on northbound and southbound SR 426 from Eastbrook Blvd. to Unnamed canal near Forsyth Rd. in Orange County. The approximate length of the project is 0.289 miles, and it is in Orange County.

Call Order: 011 Proposal: T5874

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45077515201)	LS	1.000
	0101- 1-	MOBILIZATION (45128225201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45077515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45128225201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	172.000
	0102- 60-	WORK ZONE SIGN	ED	38,189.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	198,019.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,376.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	5,824.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,038.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,870.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,870.000
	0102-115-	TYPE III BARRICADE	ED	4,592.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,286.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	42.000
	0107- 1-	LITTER REMOVAL	AC	46.340
	0107- 2-	MOWING	AC	1.750
	0110- 1- 1	CLEARING & GRUBBING (45077515201)	LS	1.000

Call Order: 011 Proposal: T5874

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (45128225201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,102.000
	0160- 4-	TYPE B STABILIZATION	SY	288.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	137.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	10,131.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	53,906.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,697.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	22.600
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	5,295.200
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	69.100
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	1.000
	0425- 1-203	INLETS, CURB, TYPE 9, J BOT, <10'	EA	2.000
	0425- 1-335	INLETS, CURB, TYPE P-3, PARTIAL	EA	1.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	13.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	3.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	7.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	2.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	7.000
	0425- 5-	MANHOLE, ADJUST	EA	7.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	112.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	429.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	34.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	19.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	202.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	874.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	4,687.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	229.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	817.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	147.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	144.000
	0521- 72- 43	SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER	LF	615.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,584.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	956.000
	0526- 1- 1	PAVERS, ARCHITECTURAL, ROADWAY	SY	594.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	44.000
	0526- 1-101	PAVERS, ARCHITECTURAL, REMOVE EXISTING AND REINSTALL	SY	70.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,141.000
	0536- 73-	GUARDRAIL REMOVAL	LF	404.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	527.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	10.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	345.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000

Call Order: 011 Proposal: T5874

ALT	Item	Description	Unit	Quantity
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	12.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	12.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	3.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	293.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.251
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.030
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,320.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	20.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	2,379.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.482
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.150
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	57.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	18.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.494
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.074
	0920-520-100	RAISED CROSSWALK, TYPE RC CURB WITH PLATE/GRATE	LF	216.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45077515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45128225201)	LS	1.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (45128225202)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	60.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	25.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	31.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	35.000
	0700- 4-612	OVERHEAD STATIC SIGN STRUCTURE, DEEP FOUNDATION REMOVAL, CANTILEVER	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	2.000
	0700-141-903	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, REMOVE - OVERHEAD MOUNT	EA	1.000
	0700-142-131	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/EDS, UP TO 12 SF OF STATIC SIGN PANELS	EA	2.000
	0700-142-132	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/EDS, 12-20 SF OF STATIC SIGN PANELS	EA	4.000
	0700-142-140	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	7.000

Call Order: 011 Proposal: T5874

ALT	Item	Description	Unit	Quantity
	0700-142-141	ENHANCED HWY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/HIGHLIGHTED SIGN <12 SF, UP TO 12 SF OF STATIC PANELS	EA	1.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	5.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	27.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,700.000
	0706- 1-110	RAISED PAVEMENT MARKER, TYPE F INTERNALLY ILLUMINATED	EA	146.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45077515201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45128225201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.060
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,166.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	99.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	958.000
	0711- 11-130	THERMOPLASTIC, STANDARD, WHITE, VERTICAL DEFLECTION MARKING	EA	58.000
	0711- 11-140	THERMOPLASTIC, STANDARD, WHITE, VERTICAL DEFLECTION ADVANCE WARNING MARKING	EA	44.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.281
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	24.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	40.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	701.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.158
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	3,746.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	16.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.838
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.010
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.162
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	113.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,254.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	32.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	5,301.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	5.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	5.000
	0715- 61-100	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 0' ARM LENGTH	EA	1.000
	0715- 61-111	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 8' ARM LENGTH	EA	7.000

Call Order: 011 Proposal: T5874

ALT	Item	Description	Unit	Quantity
	0715- 62-111	LIGHT POLE COMPLETE, F&I, STANDARD POLE SPECIAL FOUNDATION, 30' MOUNTING HEIGHT, 8' ARM LENGTH	EA	5.000
	0715- 62-121	LIGHT POLE COMPLETE, F&I, STANDARD POLE SPECIAL FOUNDATION, 30' MOUNTING HEIGHT, 10' ARM LENGTH	EA	1.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	3.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	14.000
Section 0004 Signalization				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	1.811
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	7.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,812.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	10,218.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	260.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	8.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	4.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	1,032.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	10,962.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	128.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	8.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	8.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	96.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	8.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	425.000
	0634- 4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	1.000
	0634- 4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	1.000
	0634- 4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	59.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	14.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	9.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	9.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	6.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	1,283.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	5.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	10.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	6.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	32.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	6.000
	0649- 21- 2	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 30'-30'	EA	1.000

Call Order: 011 Proposal: T5874

ALT	Item	Description	Unit	Quantity
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	6.000
	0650- 1- 15	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 2-4 WAYS	AS	4.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	3.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	12.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	12.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	39.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	23.000
	0654- 3- 10	MIDBLOCK CROSSWALK: PEDESTRIAN HYBRID BEACON ASSEMBLY, FURNISH & INSTALL COMPLETE ASSEMBLY	AS	12.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	4.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	22.000
	0660- 4- 60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	3.000
	0660- 9- 11	TRAFFIC DATA DETECTION SYSTEM- VIDEO, FURNISH AND INSTALL, CABINET EQUIPMENT	EA	4.000
	0660- 9- 12	TRAFFIC DATA DETECTION SYSTEM- VIDEO, FURNISH AND INSTALL, ABOVE GROUND EQUIPMENT	EA	5.000
	0663- 1-111	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, CABINET ELECTRONICS	EA	4.000
	0663- 1-112	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, DETECTOR	EA	12.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	39.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	2.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	23.000
	0670- 5-160	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA W/STANDARD LOCK	AS	7.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	3.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	1.000
	0682- 1-173	ITS CCTV CAMERA, NON-PRESSURIZED, IP, HIGH DEFINITION	EA	3.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	8.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	6.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	7.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	6.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	10.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	16.000

Call Order: 011 Proposal: T5874

ALT	Item	Description	Unit	Quantity
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	1.000
	0700-141-161	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, BLANK OUT SIGN <12 SF, UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000