

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: CT260429 Call Order: 004 Proposal: T3996 District:03  
 Counties: WASHINGTON  
 Road Name: SR 77 (MAIN ST)  
 Limits: FROM S OF 5TH ST TO S OF SR 273 (GLENWOOD AVE)  
 Project(s): 45080215201(\*) Federal Aid No: D325045B  
 Project(s): 45080215202 Federal Aid No: N/A  
 Total Roadway Length: 1.535 Miles Contract Days: 120  
 Total Bridge Length: 0.000 Miles Letting Date: 04/29/26  
 Total Proposal Length: 1.535 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 120 Days  
 Proposal Budget Estimate: \$1,715,920.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing SR 77 (Main St.) from south of 5th St. to south of SR 273 (Glenwood Ave.), intersection improvements at SR 10 (US 90) (Jackson Ave.), select roadway reconstruction, drainage and signalization improvement under FPID 450802-1-52-0. Additionally, utility adjustments will be included under FPID 450802-1-52-02. All work is in Washington County.

**Call Order: 004 Proposal: T3996**

| ALT                         | Item        | Description  | Unit | Quantity  |
|-----------------------------|-------------|--|------|-----------|
| <b>Section 0001 Roadway</b> |             |  |      |           |
|                             | 0101- 1-    | MOBILIZATION (45080215201)   | LS   | 1.000     |
|                             | 0102- 1-    | MAINTENANCE OF TRAFFIC (45080215201)                                   | LS   | 1.000     |
|                             | 0102- 14-   | TRAFFIC CONTROL OFFICER  | HR   | 236.000   |
|                             | 0102- 60-   | WORK ZONE SIGN   | ED   | 7,710.000 |
|                             | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD                 | ED   | 1,207.000 |
|                             | 0102- 74- 8 | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | FD   | 156.000   |
|                             | 0102- 99-   | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY                            | ED   | 271.000   |
|                             | 0102-104-   | TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION                  | ED   | 360.000   |
|                             | 0102-107- 1 | TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION              | ED   | 360.000   |
|                             | 0102-115-   | TYPE III BARRICADE   | ED   | 6.000     |
|                             | 0104- 10- 3 | SEDIMENT BARRIER   | LF   | 389.000   |
|                             | 0104- 18-   | INLET PROTECTION SYSTEM  | EA   | 19.000    |
|                             | 0107- 1-    | LITTER REMOVAL   | AC   | 33.140    |
|                             | 0107- 2-    | MOWING   | AC   | 28.960    |
|                             | 0110- 1- 1  | CLEARING & GRUBBING (45080215201)                                      | LS   | 1.000     |
|                             | 0110- 2- 2  | SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN            | AC   | 0.010     |
|                             | 0110- 4- 10 | REMOVAL OF EXISTING CONCRETE   | SY   | 174.000   |
|                             | 0110- 21-   | TREE PROTECTION BARRIER  | LF   | 25.000    |
|                             | 0120- 2- 2  | BORROW EXCAVATION, TRUCK MEASURE                                       | CY   | 174.400   |
|                             | 0160- 4-    | TYPE B STABILIZATION   | SY   | 157.000   |
|                             | 0285-706-   | OPTIONAL BASE, BASE GROUP 06   | SY   | 153.000   |

**Call Order: 004 Proposal: T3996**

| ALT | Item                        | Description   | Unit | Quantity   |
|-----|-----------------------------|---|------|------------|
|     | 0285-711-                   | OPTIONAL BASE, BASE GROUP 11  | SY   | 99.000     |
|     | 0327- 70- 5                 | MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH   | SY   | 23,111.000 |
|     | 0327- 70- 6                 | MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH   | SY   | 4,787.000  |
|     | 0327- 70- 7                 | MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH   | SY   | 7,974.000  |
|     | 0334- 1- 53                 | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22  | TN   | 904.800    |
|     | 0337- 7- 83                 | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22                              | TN   | 3,791.000  |
|     | 0425- 1-341                 | INLETS, CURB, TYPE P-4, <10'  | EA   | 1.000      |
|     | 0425- 2- 63                 | MANHOLES, P-8, PARTIAL  | EA   | 1.000      |
|     | 0430-175-115                | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD   | LF   | 22.000     |
|     | 0520- 1- 10                 | CONCRETE CURB & GUTTER, TYPE F  | LF   | 157.000    |
|     | 0520- 1- 12                 | CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE                                  | LF   | 29.000     |
|     | 0522- 2-                    | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK   | SY   | 112.000    |
|     | 0527- 2-                    | DETECTABLE WARNINGS   | SF   | 82.000     |
|     | 0570- 1- 2                  | PERFORMANCE TURF, SOD   | SY   | 889.000    |
|     | 0706- 1- 3                  | RAISED PAVEMENT MARKER, TYPE B  | EA   | 103.000    |
|     | 0710- 11-101                | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"                                       | GM   | 0.550      |
|     | 0710- 11-102                | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"      | GM   | 0.013      |
|     | 0710- 11-123                | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"         | LF   | 301.000    |
|     | 0710- 11-124                | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"              | LF   | 91.000     |
|     | 0710- 11-125                | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"           | LF   | 322.000    |
|     | 0710- 11-170                | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS  | EA   | 5.000      |
|     | 0710- 11-201                | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"                                      | GM   | 0.509      |
|     | 0710- 11-241                | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6" | GM   | 0.131      |
|     | 0999- 25-                   | INITIAL CONTINGENCY AMOUNT, DO NOT BID (45080215201)  | LS   | 1.000      |
|     | <b>Section 0002 Signing</b> |   |      |            |
|     | 0700- 1-111                 | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF                       | EA   | 4.000      |
|     | 0700- 1-112                 | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF                          | EA   | 1.000      |
|     | 0700- 1-500                 | SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE  | EA   | 1.000      |
|     | 0700- 1-600                 | SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE  | EA   | 2.000      |
|     | 0706- 1- 3                  | RAISED PAVEMENT MARKER, TYPE B  | EA   | 832.000    |
|     | 0710- 90-                   | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45080215201)                                      | LS   | 1.000      |
|     | 0711- 11-123                | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT                     | LF   | 2,046.000  |
|     | 0711- 11-124                | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS                       | LF   | 292.000    |
|     | 0711- 11-125                | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK                      | LF   | 480.000    |
|     | 0711- 11-160                | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL   | EA   | 2.000      |
|     | 0711- 11-170                | THERMOPLASTIC, STANDARD, WHITE, ARROW   | EA   | 40.000     |

**Call Order: 004 Proposal: T3996**

| ALT                               | Item         | Description   | Unit | Quantity  |
|-----------------------------------|--------------|---|------|-----------|
|                                   | 0711- 11-180 | THERMOPLASTIC, STANDARD, WHITE, YIELD LINE  | LF   | 13.000    |
|                                   | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON                                   | LF   | 460.000   |
|                                   | 0711- 11-241 | THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"                | GM   | 0.131     |
|                                   | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK   | LF   | 1,087.000 |
|                                   | 0711- 14-191 | THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE   | LF   | 51.000    |
|                                   | 0711- 14-193 | THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE                    | LF   | 286.000   |
|                                   | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"  | GM   | 3.095     |
|                                   | 0711- 16-102 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"  | GM   | 0.099     |
|                                   | 0711- 16-131 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP                   | GM   | 0.004     |
|                                   | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"   | GM   | 3.111     |
|                                   | 0711- 16-231 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"  | GM   | 0.428     |
|                                   | 0711- 17- 1  | THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN                     | SF   | 45.000    |
| <b>Section 0003 Signalization</b> |              |   |      |           |
|                                   | 0630- 2- 11  | CONDUIT, FURNISH & INSTALL, OPEN TRENCH   | LF   | 3.000     |
|                                   | 0630- 2- 12  | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE  | LF   | 143.000   |
|                                   | 0632- 7- 1   | SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL                                    | PI   | 2.000     |
|                                   | 0632- 7- 6   | SIGNAL CABLE, REMOVE- INTERSECTION  | PI   | 2.000     |
|                                   | 0635- 2- 11  | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE  | EA   | 7.000     |
|                                   | 0646- 1- 11  | ALUMINUM SIGNALS POLE, PEDESTAL   | EA   | 1.000     |
|                                   | 0646- 1- 60  | ALUMINUM SIGNALS POLE, REMOVE   | EA   | 2.000     |
|                                   | 0650- 2-109  | VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED | EA   | 8.000     |
|                                   | 0653- 1- 12  | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS  | AS   | 1.000     |
|                                   | 0660- 2-101  | LOOP ASSEMBLY- F&I, TYPE A  | AS   | 12.000    |
|                                   | 0660- 2-102  | LOOP ASSEMBLY, F&I, TYPE B  | AS   | 2.000     |
|                                   | 0660- 2-106  | LOOP ASSEMBLY, F&I, TYPE F  | AS   | 10.000    |
|                                   | 0665- 1- 11  | PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD  | EA   | 4.000     |
|                                   | 0665- 1- 50  | PEDESTRIAN DETECTOR, ADJUST/MODIFY ON EXISTING POLE   | EA   | 1.000     |
|                                   | 0665- 1- 60  | PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN  | EA   | 2.000     |
|                                   | 0700- 5- 22  | INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF                              | EA   | 4.000     |
| <b>Section 0004 Utilities</b>     |              |   |      |           |
|                                   | 0425- 5-     | MANHOLE, ADJUST   | EA   | 3.000     |
|                                   | 0425- 5- 1   | MANHOLE, ADJUST, UTILITIES  | EA   | 20.000    |
|                                   | 0425- 6-     | VALVE BOXES, ADJUST   | EA   | 20.000    |