

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	07250910	Call Order: 001	Proposal: E7U02	District:07
Counties:	HERNANDO			
Road Name:	US 98/SR 700 - RESURFACING			
Limits:	08080000			
Project(s):	43673315201(*)	Federal Aid No:	N/A	
Total Roadway Length:	2.488 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	09/10/25	
Total Proposal Length:	2.488 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days Acquis.	
Proposal Budget Estimate:	\$4,652,720.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing on US98 /SR700/Ponce De Leon Blvd. From N of CR491 to N of Landfill Rd. in Hernando County.

Prequalification required.

Call Order: 001 Proposal: E7U02

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43673315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43673315201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	4,320.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,440.000
	0102- 60-	WORK ZONE SIGN	ED	5,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	42,480.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	388.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	140.000
	0107- 1-	LITTER REMOVAL	AC	308.620
	0107- 2-	MOWING	AC	308.620
	0110- 1- 1	CLEARING & GRUBBING (43673315201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	67.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	1.000
	0120- 6-	EMBANKMENT	CY	1.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43673315201)	LS	1.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	161.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	23.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	45,989.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	3,146.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,720.000
	0327- 70- 16	MILLING EXISTING ASPHALT PAVEMENT, 1/2" AVG DEPTH	SY	10,607.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	510.500
	0334- 1- 57	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, HIGH POLYMER	TN	7,805.200

Call Order: 001 Proposal: E7U02

ALT	Item	Description	Unit	Quantity
	0337- 7- 93	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, HIGH POLYMER	TN	4,166.500
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	14.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	2.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	1.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	50.000
	0570- 1- 1	PERFORMANCE TURF	SY	89.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,623.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	3,501.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	72.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	2.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	816.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	10.274
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.168
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	210.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	68.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.244
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.166
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	32.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	8.854
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	630.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.502
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.172
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43673315201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	6.555
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	20.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	16.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	7.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	816.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43673315201)	LS	1.000

Call Order: 001 Proposal: E7U02

ALT	Item	Description	Unit	Quantity
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	105.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	34.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.083
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	16.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	315.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.086
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.137
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.084
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.122
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.427
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.751