

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260930	Call Order: 005	Proposal: T2A79	District:02
Counties:	COLUMBIA			
Road Name:	SR 25 (US 41)			
Limits:	FROM N OF SR 8 (I-10) TO HAMILTON CO LINE			
Project(s):	20838955201(*)	Federal Aid No:	D226055B	
Total Roadway Length:	6.559 Miles	Contract Days:	180	
Total Bridge Length:	0.084 Miles	Letting Date:	09/30/26	
Total Proposal Length:	6.643 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$6,182,385.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, base work, drainage improvements, highway signing, guardrail, and other incidental construction on SR 25 (US 41) in Columbia County from North of I-10 (SR 8) to the Hamilton County Line.

Call Order: 005 Proposal: T2A79

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (20838955201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (20838955201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (20838955201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (20838955201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	14,915.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,588.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	1,462.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	26,296.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	1,483.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	2,420.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	13.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	682.000
	0102-115-	TYPE III BARRICADE	ED	630.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	55.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,693.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	1,309.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	7.000
	0107- 1-	LITTER REMOVAL	AC	744.220
	0107- 2-	MOWING	AC	504.310
	0110- 1- 1	CLEARING & GRUBBING (20838955201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	2.000
	0120- 1-	REGULAR EXCAVATION	CY	390.300

Call Order: 005 Proposal: T2A79

ALT	Item	Description	Unit	Quantity
	0120- 6-	EMBANKMENT	CY	115.700
	0160- 4-	TYPE B STABILIZATION	SY	563.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,675.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	164.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	1,757.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	92,708.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	45,874.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	703.600
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	7,854.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	10,879.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	89.100
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	182.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	83.000
	0430-542-100	STRAIGHT CONCRETE ENDWALLS, 42", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	10.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	3.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	112.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	14.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	15.700
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	2.000
	0530- 74-	BEDDING STONE	TN	7.300
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	763.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	452.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	6.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,518.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	3,002.200
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	14.163
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	141.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	357.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.185
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	8.864
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	3.940
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20838955201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	18.743
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	32.000

Call Order: 005 Proposal: T2A79

ALT	Item	Description	Unit	Quantity
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	26.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	41.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	3.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	56.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	53.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,582.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (20838955201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	141.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	357.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.185
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	13.086
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	7.685
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	3.940