

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251029	Call Order: 015	Proposal: T5869	District:05
Counties:	MARION			
Road Name:	SR 40 (E SILVER SPRINGS BLVD)			
Limits:	FROM US 441 TO SE 196 TERRACE RD			
Project(s):	45094815201(*)	Federal Aid No:	D524039B	
Project(s):	45095115201	Federal Aid No:	N/A	
Project(s):	45095215201	Federal Aid No:	N/A	
Total Roadway Length:	20.119 Miles	Contract Days:	420	
Total Bridge Length:	0.524 Miles	Letting Date:	10/29/25	
Total Proposal Length:	20.643 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$18,921,582.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, signalization, signing/pavement markings, and lighting on SR 40 from US 441 to SE 196 Terrace Rd for approximately 20.119 miles in Marion County.

Call Order: 015 Proposal: T5869

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45094815201)	LS	1.000
	0101- 1-	MOBILIZATION (45095115201)	LS	1.000
	0101- 1-	MOBILIZATION (45095215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45094815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45095115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45095215201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45095115201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45095215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,286.000
	0102- 60-	WORK ZONE SIGN	ED	132,048.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	164,640.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,279.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,714.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	7,048.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	8,820.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	8,820.000
	0102-115-	TYPE III BARRICADE	ED	1,843.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	420.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.101
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.185
	0104- 10- 3	SEDIMENT BARRIER	LF	4,400.000

Call Order: 015 Proposal: T5869

ALT	Item	Description	Unit	Quantity
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	107.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	139.000
	0107- 1-	LITTER REMOVAL	AC	4,955.890
	0107- 2-	MOWING	AC	4,599.300
	0110- 1- 1	CLEARING & GRUBBING (45094815201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45095115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45095215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	522.000
	0120- 1-	REGULAR EXCAVATION	CY	75.500
	0120- 6-	EMBANKMENT	CY	54.200
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	102.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	33.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	69,204.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	56,990.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	462,912.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	5,717.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	23,841.000
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC E, FC-12.5, PG 76-22	TN	26,338.600
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	4.000
	0425- 82-	REPLACE GRATE	EA	2.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	246.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	179.000
	0430-602-125	U-ENDWALL, WITH GRATE,INDEX 260/430-010, 1:4 SLOPE, 18"	EA	1.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	2.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	575.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	414.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	325.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,494.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	48,258.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	328.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	150.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	14.000
	0639- 8-151	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), CLAY ELECTRIC (DO NOT BID) (45094815201)	LS	1.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	29.000
	0695- 3- 11	TRAFFIC MONITORING SITE SPEED/CLASSIFICATION UNIT, FURNISH & INSTALL, VOLUME SPEED AND CLASSIFICATION	AS	1.000
	0695- 5- 1	TRAFFIC MONITORING SITE SOLAR POWER UNIT, FURNISH & INSTALL	EA	1.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	29.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	4.000

Call Order: 015 Proposal: T5869

ALT	Item	Description	Unit	Quantity
	0695- 7-162	TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	EA	1.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	5.000
	0695- 16- 1	TRAFFIC MONITORING SITE SURGE SUPPRESSOR, FURNISH & INSTALL	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,160.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	5.979
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.103
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	6,551.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	63.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,612.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	3.875
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.593
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	129.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	27.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.085
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,149.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.824
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.036
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	10.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45094815201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45095115201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45095215201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	36.444
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	295.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	46.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	5.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	3.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	87.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	3.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	3.000

Call Order: 015 Proposal: T5869

ALT	Item	Description	Unit	Quantity
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	8.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	6.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-105	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 51-100 SF	EA	1.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	1.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	148.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	101.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	4.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	55.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	20.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	47.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	11,373.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	40.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	4.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	149.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45094815201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45095115201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45095215201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.057
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	11,945.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,405.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	3,429.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.604
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	67.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	589.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	154.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	8,382.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.851
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	6,618.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	4.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	4.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	50.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	300.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	43.545

Call Order: 015 Proposal: T5869

ALT	Item	Description	Unit	Quantity
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	1.279
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	14.010
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.145
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	43.369
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	6.770
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	189.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	28.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,487.000
	0715- 61-321	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 10' ARM LENGTH	EA	3.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	3.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	70.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	186.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	4.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	420.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	39.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	22.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	20.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	54.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	84.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	75.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	15.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	5.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	6.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000