

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 005	Proposal: T2A82	District:02
Counties:	ALACHUA			
Road Name:	SR 24A / SR 226 (SW 16TH AVE)			
Limits:	FROM SR 24 (ARCHER RD) TO SR 331 (SE WILLISTON RD)			
Project(s):	20755545201(*)	Federal Aid No:	D226052B	
Total Roadway Length:	2.131 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	10/28/26	
Total Proposal Length:	2.171 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$3,086,851.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, shoulder treatment, drainage improvements, curb & gutter, traffic signals, highway signing, sidewalks, and other incidental construction on SR 24A/ SR 226 (SW 16th Ave) from SR 24 (Archer Rd) to SR 331 (SE Williston Rd) in Alachua County.

Call Order: 005 Proposal: T2A82

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (20755545201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (20755545201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (20755545201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	192.000
	0102- 60-	WORK ZONE SIGN	ED	13,350.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	74,098.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,454.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	600.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	2,036.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,312.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,200.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,200.000
	0102-913- 24	REMOVABLE TAPE, WHITE, 12" CROSSWALK	LF	56.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,496.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	72.000
	0107- 1-	LITTER REMOVAL	AC	65.400
	0107- 2-	MOWING	AC	50.940
	0110- 1- 1	CLEARING & GRUBBING (20755545201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	589.000
	0120- 1-	REGULAR EXCAVATION	CY	0.300
	0120- 6-	EMBANKMENT	CY	56.700
	0160- 4-	TYPE B STABILIZATION	SY	536.000

Call Order: 005 Proposal: T2A82

ALT	Item	Description	Unit	Quantity
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	81,535.000
	0337- 7- 93	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, HIGH POLYMER	TN	8,968.900
	0425- 5-	MANHOLE, ADJUST	EA	4.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	21.000
	0425- 6-	VALVE BOXES, ADJUST	EA	10.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	607.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	453.000
	0527- 2-	DETECTABLE WARNINGS	SF	497.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,084.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	5.808
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	2.715
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.282
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20755545201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	15.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	9.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	6.000
	0700-142-111	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	2.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,036.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (20755545201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.053
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,119.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,764.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	808.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.795
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	82.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	13.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	572.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.314
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	3,403.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	37.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	37.000

Call Order: 005 Proposal: T2A82

ALT	Item	Description	Unit	Quantity
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.808
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.715
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.048
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.282
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.424
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	16.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	179.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	11.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	1.000
	0660- 2-103	LOOP ASSEMBLY, F&I, TYPE C	AS	5.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	1.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	1.000