

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 07250813      Call Order: 002      Proposal: E7U09      District:07  
Counties: HILLSBOROUGH  
Road Name: HILLSBOROUGH COUNTY LONG BRIDGE REPAIRS  
Limits: 10060000  
Project(s): 44998215201(\*)      Federal Aid No: N/A  
Total Roadway Length: 0.298 Miles      Contract Days: 380  
Total Bridge Length: 0.593 Miles      Letting Date: 08/13/25  
Total Proposal Length: 0.891 Miles      Contract Execution Days: 10  
Special Start Date: N/A  
Aquis/Flexible Start Time: 120 Days Acquis.  
Proposal Budget Estimate: \$3,527,480.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of bridge repairs including spall and crack repairs, bridge jacking and bearing shim installation, placement of structural cathodic protection pile jackets, and steel painting on Bridge Nos. 100107 and 100045 at SR 45 (US 41) over Alafia River; additionally, spall and crack repairs and installation of polymer nosing on Bridge Nos.100267 and 100268 at SR 583 (N. 56th Street) over Hillsborough River in Hillsborough County.

Prequalification required.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 002 Proposal: E7U09**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0400-140- 1	NEOPRENE PAD REPLACEMENT, BENT/PIER	EA	13.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	45.200
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	76.200
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	1.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	3.000
	0457- 2-221	CATHODIC PROTECTION INTEGRAL PILE JACKET, STRUCTURAL, 16.1-30.", GALVANIC SYSTEM	LF	168.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	447.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	113.300
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (44998215201)	LS	1.000
	0561- 2-	COATING EXISTING STRUCTURAL STEEL	SF	585.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (44998215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44998215201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	2,520.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	4,526.000
	0102- 60-	WORK ZONE SIGN	ED	6,945.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	24,557.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	996.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	380.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	497.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	2,600.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44998215201)	LS	1.000