

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260930	Call Order: 003	Proposal: T1944	District:01
Counties:	HENDRY			
Road Name:	HOMESTEAD AVE			
Limits:	OVER MARSH CREEK, BRIDGE NO 074026			
Project(s):	44723815201(*)	Federal Aid No: D126064B		
Total Roadway Length:	0.349 Miles	Contract Days:	300	
Total Bridge Length:	0.011 Miles	Letting Date:	09/30/26	
Total Proposal Length:	0.360 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	

Proposal Budget Estimate: \$1,671,747.00

Please read the full advertisement

Description:

The Improvements under this contract consist of bridge replacement, milling and resurfacing, drainage, guardrail and signing and pavement markings along Homestead Avenue over Marsh Creek in Hendry County.

Call Order: 003 Proposal: T1944

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	84.500
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	45.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	33.500
	0400- 7- 1	BRIDGE DECK GROOVING	SY	186.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	2.700
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	25,042.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	7,037.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	10,568.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	10.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	484.000
	0455-115-	PILE REDRIVE	EA	3.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	11.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	3.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	154.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	56.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	203.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	19.300
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	354.900
	0530- 74-	BEDDING STONE	TN	255.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44723815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44723815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,700.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,428.000
	0102-115-	TYPE III BARRICADE	ED	1,500.000

Call Order: 003 Proposal: T1944

ALT	Item	Description	Unit	Quantity
	0104- 10- 3	SEDIMENT BARRIER	LF	122.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	481.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	44.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	6.000
	0110- 1- 1	CLEARING & GRUBBING (44723815201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	1,059.800
	0120- 6-	EMBANKMENT	CY	703.900
	0160- 4-	TYPE B STABILIZATION	SY	1,059.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	951.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	79.600
	0425- 1-523	INLETS, DT BOT, TYPE C,JBOT, <10'	EA	2.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	426.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	0.700
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	2.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	8.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	17.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	91.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	20.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	29.000
	0536- 73-	GUARDRAIL REMOVAL	LF	220.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	553.000
Section 0003 Signing				
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	14.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44723815201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	56.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.054
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.070
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.025