

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250730	Call Order: 017	Proposal: T5819	District:05
Counties:	LAKE			
Road Name:	SR 33 (CR 33)			
Limits:	FROM S OF EDGEWOOD BOYS RANCH RD TO S OF WRIGHT ST			
Project(s):	44568515201(*)	Federal Aid No:	D521057B	
Total Roadway Length:	1.908 Miles	Contract Days:	270	
Total Bridge Length:	0.000 Miles	Letting Date:	07/30/25	
Total Proposal Length:	1.908 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$7,640,997.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of intermittent shoulder replacement & widening (in curved roadway segments), mainline widening to accommodate a new southbound to eastbound left turn lane from SR 33 to CR 565B (Pine Island Rd.); a new southbound to eastbound left turn lane from SR 33 to Groveland Airport Road; a new sidewalk from Domenico Ct. to Parkwood St., and milling and resurfacing of contiguous roadway.

Call Order: 017 Proposal: T5819

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44568515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44568515201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44568515201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44568515201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	59.300
	0102- 60-	WORK ZONE SIGN	ED	3,246.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	1,750.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	4,575.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	16,990.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	3,428.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	24.000
	0102-115-	TYPE III BARRICADE	ED	2,178.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	130.000
	0104- 10- 3	SEDIMENT BARRIER	LF	9,539.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	796.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	13.000
	0107- 1-	LITTER REMOVAL	AC	49.080
	0107- 2-	MOWING	AC	54.410
	0110- 1- 1	CLEARING & GRUBBING (44568515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	189.000
	0120- 1-	REGULAR EXCAVATION	CY	2,460.500
	0120- 4-	SUBSOIL EXCAVATION	CY	138.100

Call Order: 017 Proposal: T5819

ALT	Item	Description	Unit	Quantity
	0120- 6-	EMBANKMENT	CY	1,510.800
	0160- 4-	TYPE B STABILIZATION	SY	8,587.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	254.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	82.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	6,002.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	3,731.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	13,744.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,249.000
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	1,796.300
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, PG 76-22	TN	1,902.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	83.800
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	454.200
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	7.000
	0425- 1-529	INLETS, DT BOT, TYPE C, MODIFY	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	6.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	80.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	864.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	49.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	5.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-530-100	STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	4.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	2,269.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	3,157.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	153.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,578.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	8.000
	0527- 2-	DETECTABLE WARNINGS	SF	153.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,650.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	1,556.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	9.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	304.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	12.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,872.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.935
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	6.937
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000

Call Order: 017 Proposal: T5819

ALT	Item	Description	Unit	Quantity
Section 0002 Signing				
	0654- 2- 22	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSEMBLY- BACK TO BACK	AS	2.000
	0701- 18-101	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	2.405
	0701- 18-201	PROFIED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	2.883
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	478.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44568515201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	448.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	65.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	10.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	338.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	50.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.164
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.020
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	4,822.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,106.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	49.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	20,206.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	2,326.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 61-211	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 8' ARM LENGTH	EA	3.000
	0715- 61-242	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 12' ARM LENGTH	EA	25.000
	0715- 61-311	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 8' ARM LENGTH	EA	13.000
	0715- 61-342	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 12' ARM LENGTH	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	43.000