

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 001	Proposal: T1937	District:01
Counties:	HARDEE			
Road Name:	SR 35 (US 17)			
Limits:	FROM N OF SR 60 TO BELL ST AND FROM S OF HEARTLAND WAY TO N OF HILTON RD			
Project(s):	44620415201	Federal Aid No:	N/A	
Project(s):	44620515201(*)	Federal Aid No:	D126072B	
Project(s):	44620515202	Federal Aid No:	D126072B	
Total Roadway Length:	13.175 Miles	Contract Days:	425	
Total Bridge Length:	0.225 Miles	Letting Date:	10/28/26	
Total Proposal Length:	13.400 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	

Proposal Budget Estimate: \$26,702,717.00

Please read the full advertisement

Description:

The Improvements under this contract consist of bridge widening, milling and resurfacing, drainage, curb and gutter, guardrail, sidewalk, signalization, and signing and pavement markings on SR 35 (US 17) from North of SR 64 to Bell Street and SR 35 (US 17) from South of Heartland Way to North of Hilton Road in Hardee County.

Call Order: 001 Proposal: T1937

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44620515202)	LS	1.000
	0121- 70-	FLOWABLE FILL	CY	4.700
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	39.700
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	20.600
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	27.500
	0400- 7- 1	BRIDGE DECK GROOVING	SY	37.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	159.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	0.700
	0405- 70- 1	LATEX MODIFIED PORTLAND CEMENT CONCRETE, TYPE I	CF	50.800
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	7,983.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	3,906.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	4,391.000
	0450- 2- 54	PREST BEAMS: FLORIDA-I BEAM 54"	LF	119.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	4.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	140.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	4.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	282.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	30.100
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	30.000
	0515- 4- 2	BULLET RAIL, DOUBLE RAIL	LF	182.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	182.000
	0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	182.000

Call Order: 001 Proposal: T1937

ALT	Item	Description	Unit	Quantity
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	10.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	346.600
	0530- 3- 8	RIPRAP- RUBBLE, REMOVE EXISTING AND REINSTALL	CY	8.400
	0530- 74-	BEDDING STONE	TN	118.500
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44620415201)	LS	1.000
	0101- 1-	MOBILIZATION (44620515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44620415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44620515201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44620515201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44620515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	3,720.000
	0102- 60-	WORK ZONE SIGN	ED	132,137.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	5,712.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	4,538.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	245,392.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	118,180.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	2,125.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	8,652.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	11.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	5,212.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	4,250.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	4,250.000
	0102-115-	TYPE III BARRICADE	ED	5,550.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	4,250.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	4,250.000
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	0.072
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.093
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.072
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.093
	0104- 10- 3	SEDIMENT BARRIER	LF	56,291.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	46.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	297.000
	0107- 1-	LITTER REMOVAL	AC	1,621.450
	0107- 2-	MOWING	AC	1,369.430
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44620515201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44620515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44620415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44620515202)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,947.000
	0120- 1-	REGULAR EXCAVATION	CY	2,393.700

Call Order: 001 Proposal: T1937

ALT	Item	Description	Unit	Quantity
	0120- 4-	SUBSOIL EXCAVATION	CY	132.600
	0120- 6-	EMBANKMENT	CY	5,228.800
	0160- 4-	TYPE B STABILIZATION	SY	340.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	658.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	219.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	200.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	590.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	140,693.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	37,760.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	23,953.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	31,773.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	192,653.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	12,196.400
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	8,098.300
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	29,551.900
	0334- 1- 59	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, HIGH POLYMER	TN	1,133.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	9,008.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	11,803.600
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, PG 76-22	TN	2,515.200
	0337- 7- 95	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, HIGH POLYMER	TN	1,144.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	224.400
	0342- 1- 2	GEOSYNTHETIC INTERLAYER REINFORCEMENT SYSTEM, COMPOSITE FIBERGLASS	SY	13,339.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	863.900
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	4.000
	0425- 1-525	INLETS, DITCH BOTTOM, TYPE C, PARTIAL	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	2.000
	0425- 1-703	INLETS, GUTTER, TYPE S, J BOTTOM <10'	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	20.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	76.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	76.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	191.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	526.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	112.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	7.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	29.000
	0430-518-100	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	5.000
	0430-984-138	MITERED END SECTION, OPTIONAL ROUND, 36" SIDE DRAIN	EA	1.000

Call Order: 001 Proposal: T1937

ALT	Item	Description	Unit	Quantity
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	3.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	4.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	12.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY, 42" TYPE 1	LF	2,599.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,582.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	221.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	9,235.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,603.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	148.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,127.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	41.800
	0530- 74-	BEDDING STONE	TN	30.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	6,207.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	3,080.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	8.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	1.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	1.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	5.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	4,544.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	6.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	10.000
	0550- 10-120	FENCING, TYPE A, 5.1-6.0, STANDARD	LF	592.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	40.000
	0550- 60-224	FENCE GATE, TYPE B, DOUBLE, 18.1-20.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	42,244.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	2,624.900
	0571- 1- 12	PLASTIC EROSION MAT, TRM, TYPE 2	SY	4,776.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	23.611
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.317
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	0.208
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	9,722.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,196.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	6,605.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	30.923
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.139

Call Order: 001 Proposal: T1937

ALT	Item	Description	Unit	Quantity
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.459
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	35.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	358.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	14.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	21.834
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,367.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.976
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44620415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44620515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44620515202)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	14.861
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	153.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	57.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	19.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	5.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	171.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	5.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	8.000
	0700- 3-105	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 51-100 SF	EA	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	26.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	89.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	2.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	6.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	21.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	65.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,321.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44620415201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44620515201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.208
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	9,786.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,587.000

Call Order: 001 Proposal: T1937

ALT	Item	Description	Unit	Quantity
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	2,099.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.451
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	43.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	356.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	14.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	972.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.947
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	5,577.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	4.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	4.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	13.155
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.269
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	13.031
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	10.541
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	8.788
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.056
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	11.532
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.139
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	8.631
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	32.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.325
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.348
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.325
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.344
Section 0004 Signalization				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	425.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	4.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	51.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	24.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	8.000