

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT261028 Call Order: 003 Proposal: T1947 District:01
 Counties: HIGHLANDS
 Road Name: SR 25 (US 27) AND SR 700 (US 98)
 Limits: FROM S OF SR 66 TO N OF SR 66 AND FROM E OF SR 25 (US 27) TO E OF FLORAL DR

Project(s): 41451135201 Federal Aid No: N/A
 Project(s): 43975025201(*) Federal Aid No: D126063B
 Total Roadway Length: 5.442 Miles Contract Days: 425
 Total Bridge Length: 0.000 Miles Letting Date: 10/28/26
 Total Proposal Length: 5.442 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 120 Days
 Proposal Budget Estimate: \$16,613,704.00

Please read the full advertisement

Description:

The improvements under this contract consist of reconstruction of an intersection with concrete pavement, milling and resurfacing, drainage, curb and gutter, signalization, lighting and signing and pavement markings on SR 25 (US 27) from South of SR 66 to North of SR 66 and SR 700 (US 98) from East of SR 25 (US 27) to East of Floral Drive in Highlands County.

Call Order: 003 Proposal: T1947

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (41451135201)	LS	1.000
	0101- 1-	MOBILIZATION (43975025201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (41451135201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43975025201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43975025201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43975025201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	304.000
	0102- 60-	WORK ZONE SIGN	ED	67,717.000
	0102- 61-	BUSINESS SIGN	EA	10.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	4,284.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	9,743.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	176,298.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	4,665.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	575.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	11,416.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,377.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	850.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	850.000
	0102-115-	TYPE III BARRICADE	ED	6,838.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	75.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	3.951

Call Order: 003 Proposal: T1947

ALT	Item	Description	Unit	Quantity
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	2.175
	0102-913- 23	REMOVABLE TAPE, WHITE, 24" STOP BAR	LF	184.000
	0102-913- 29	REMOVABLE TAPE, WHITE, MESSAGE, SYMBOL OR ARROW	EA	45.000
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	1.001
	0104- 10- 3	SEDIMENT BARRIER	LF	11,663.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	6.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	7.000
	0107- 1-	LITTER REMOVAL	AC	764.260
	0107- 2-	MOWING	AC	662.600
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (41451135201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43975025201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,837.000
	0120- 1-	REGULAR EXCAVATION	CY	1,177.900
	0120- 6-	EMBANKMENT	CY	2,863.900
	0160- 4-	TYPE B STABILIZATION	SY	33,104.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,898.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	1,576.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	23,348.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,440.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	177.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	75,702.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	763.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	531.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	35,016.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	17,298.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	8,543.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	2,499.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	814.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	9,265.100
	0350- 3- 7	PLAIN CEMENT CONCRETE PAVEMENT, 9"	SY	23,009.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	29,925.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	23,009.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	2.000
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	1.000
	0425- 82-	REPLACE GRATE	EA	2.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	293.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	84.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	4.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	8.000
	0430-175-215	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 15"S/CD	LF	162.000
	0430-982-123	MITERED END SECTION, OPTIONAL ROUND, 15" CD	EA	1.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	2.000
	0430-982-623	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 15" CD	EA	1.000

Call Order: 003 Proposal: T1947

ALT	Item	Description	Unit	Quantity
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	6.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	1.000
	0446- 1- 1	EDGEDRAIN DRAINCRETE, STANDARD	LF	3,202.000
	0446- 71- 1	EDGEDRAIN OUTLET PIPE, 4"	LF	159.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	5,646.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	122.000
	0527- 2-	DETECTABLE WARNINGS	SF	16.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	41,848.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	2,286.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	19.384
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.623
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	462.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,580.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,092.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	3.173
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.673
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	49.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	316.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	15.780
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,544.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.704
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.658
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (41451135201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43975025201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	14.087
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	16.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	20.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	32.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	3.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	2.000

Call Order: 003 Proposal: T1947

ALT	Item	Description	Unit	Quantity
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	7.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	0701- 17-101	PROFIED THERMOPLASTIC,STANDARD- CONCRETE SURFACES, WHITE, SOLID,6"	GM	0.121
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	28.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,715.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (41451135201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43975025201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.040
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	901.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	442.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.218
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	9.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	65.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	2,022.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.369
	0711- 12-101	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6"	GM	0.015
	0711- 12-125	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 24" FOR STOP LINE OR CROSSWALK	LF	50.000
	0711- 12-201	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	GM	0.020
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	462.000
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.227
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	20.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	67.000
	0711- 14-241	THERMOPLASTIC, PREFORMED, YELLOW, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.103
	0711- 14-341	THERMOPLASTIC, PREFORMED, BLACK, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.165
	0711- 14-527	THERMOPLASTIC, PREFORMED, 24" WHITE WITH 4" BLACK CONTRAST FOR STOP LINE ON CONCRETE PAVEMENT, 32"	LF	153.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.871
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.190
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.042
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.635
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	10.719
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.120
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	9.941

Call Order: 003 Proposal: T1947

ALT	Item	Description	Unit	Quantity
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.704
	0713-103-121	PERMANENT TAPE, WHITE, SOLID W/CONTRAST, 6" PRIMARY LINE WIDTH, FOR CONCRETE SURFACES	GM	1.211
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.933
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.917
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,615.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	744.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	32.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	81.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	45.000
	0639- 8-100	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), DUKE (DO NOT BID) (43975025201)	LS	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	15,641.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	703.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	4.000
	0715- 61-352	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 15' ARM LENGTH	EA	16.000
	0715- 65-366	LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 16' ARM LENGTH	EA	1.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	17.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	17.000
Section 0004 Signalization				
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	185.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	470.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	10.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	95.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	10.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0649- 1- 65	STEEL STRAIN POLE, REMOVE, DEEP FOUNDATION REMOVAL, BOLT ON ATTACHMENT	EA	2.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	3.000

Call Order: 003 Proposal: T1947

ALT	Item	Description	Unit	Quantity
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	10.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	2.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	2.000
	0670- 5-161	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA W/STANDARD LOCK, 1 PREEMPTION	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0682- 1-163	ITS CCTV CAMERA, PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0684- 8- 1	CELLULAR MODEM, FURNISH AND INSTALL	EA	1.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000