

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251029	Call Order: 009	Proposal: T3975	District:03
Counties:	GULF			
Road Name:	SR 71 (CECIL G COSTINS BLVD)			
Limits:	FROM SR 30 (US 98) TO S OF PO ENTRANCE			
Project(s):	43079415201(*)	Federal Aid No:	D325001B	
Total Roadway Length:	0.413 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	10/29/25	
Total Proposal Length:	0.413 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$2,395,477.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of rigid pavement rehabilitation, flexible pavement reconstruction, base work, drainage improvements, ADA ramps, traffic signals, highway signing, sidewalks, signing and pavement markings and other incidental construction on SR 71 CECIL G COSTINS BLVD FROM SR 30 (US 98) TO S OF P.O. ENTRANCE in Gulf County.

Call Order: 009 Proposal: T3975

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43079415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43079415201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43079415201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43079415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,250.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	354.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	354.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	38,480.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	130,763.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	5,160.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	180.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	410.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	832.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-115-	TYPE III BARRICADE	ED	720.000
	0104- 10- 3	SEDIMENT BARRIER	LF	82.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	15.000
	0107- 1-	LITTER REMOVAL	AC	17.940
	0107- 2-	MOWING	AC	17.540
	0110- 1- 1	CLEARING & GRUBBING (43079415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,028.000

Call Order: 009 Proposal: T3975

ALT	Item	Description	Unit	Quantity
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43079415201)	LS	1.000
	0121- 70-	FLOWABLE FILL	CY	5.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	527.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	100.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	13.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	8.300
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	21,519.000
	0353- 70-	CONCRETE PAVEMENT SLAB REPLACEMENT	CY	617.200
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	3.000
	0425- 6-	VALVE BOXES, ADJUST	EA	7.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	4.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	4.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	8.000
	0440- 73- 2	UNDERDRAIN OUTLET PIPE, 6"	LF	36.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	279.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	51.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	184.000
	0523- 3-	PATTERNED PAVEMENT	SY	55.000
	0527- 2-	DETECTABLE WARNINGS	SF	255.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,609.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.640
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,526.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	18.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.670
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.065
	0710- 17- 1	PAINTED PAVEMENT MARKINGS, REMOVAL OF NON-CONFLICTING	SF	15,748.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43079415201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	24.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	9.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	6.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	3.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	8.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	710.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43079415201)	LS	1.000
	0711- 14-527	THERMOPLASTIC, PREFORMED, 24" WHITE WITH 4" BLACK CONTRAST FOR STOP LINE ON CONCRETE PAVEMENT, 32"	LF	176.000

Call Order: 009 Proposal: T3975

ALT	Item	Description	Unit	Quantity
	0711- 14-528	THERMOPLASTIC, PREFORMED, 12" WHITE WITH 4" BLACK CONTRAST FOR CROSSWALK ON CONCRETE PAVEMENT, 20"	LF	781.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	56.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	20.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.929
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.011
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.811
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	14,364.000
	0713-103-121	PERMANENT TAPE, WHITE, SOLID W/CONTRAST, 6" PRIMARY LINE WIDTH, FOR CONCRETE SURFACES	GM	0.019
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.693
	0713-103-241	PERMANENT TAPE, YELLOW, 6-10 DOTTED EXTENSION, 6" WIDE, FOR CONCRETE SURFACES	GM	0.125
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.693