

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: CT260429      Call Order: 003      Proposal: T3995      District:03

Counties: JACKSON

Road Name: SR 8 (I-10)

Limits: FROM WASHINGTON CO LINE TO E OF SR 276

Project(s): 45069115201(\*)      Federal Aid No: D325044B

Total Roadway Length:	10.144 Miles	Contract Days:	400
Total Bridge Length:	0.116 Miles	Letting Date:	04/29/26
Total Proposal Length:	10.260 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120 Days

Proposal Budget Estimate: \$14,985,360.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of FPID 450691-1-52-01, SR 8 (I-10) from Washington County Line to East of SR 276 in Jackson County. Existing travel lanes, auxiliary lanes, median crossovers, and paved shoulders will be milled and resurfaced. Other improvements include signing and pavement markings.

**Call Order: 003 Proposal: T3995**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (45069115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45069115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,326.000
	0102- 60-	WORK ZONE SIGN	ED	18,540.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	97,236.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	300.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	3,424.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	600.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	600.000
	0104- 10- 3	SEDIMENT BARRIER	LF	11,659.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	36.000
	0107- 1-	LITTER REMOVAL	AC	4,602.320
	0107- 2-	MOWING	AC	4,203.140
	0110- 1- 1	CLEARING & GRUBBING (45069115201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	2,047.100
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,926.000
	0160- 4-	TYPE B STABILIZATION	SY	6,820.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,039.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	6,406.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	33,189.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	133,180.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	330,421.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	11,396.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	9,090.200
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	30,043.800

**Call Order: 003 Proposal: T3995**

ALT	Item	Description	Unit	Quantity
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	13,258.200
	0337- 7- 80	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-9.5, PG 76-22	TN	783.400
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	3,650.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2,987.100
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	82.000
	0430-612-025	U-ENDWALL WITH GRATE, INDEX 261/430-011, 1:6 SLOPE, 18"PIPE	EA	4.000
	0521- 5- 11	CONCRETE TRAFFIC RAILING- BRIDGE, RETROFIT-POST & BEAM RAILING	EA	4.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	7,280.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-002, APPROACH TL-3	EA	8.000
	0536- 73-	GUARDRAIL REMOVAL	LF	6,535.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	4.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	12.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	84,756.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	289.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	51.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	400.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	8.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	9,122.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	24.295
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.309
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	422.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,412.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	64.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	43.528
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	21.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	60.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	23.563
	0908-333-100	HIGH FRICTION SURFACE COURSE	SY	1,430.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45069115201)	LS	1.000
<b>Section 0002 Signing</b>				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	38.110
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	0.670
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	10.000

**Call Order: 003 Proposal: T3995**

ALT	Item	Description	Unit	Quantity
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	4.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	10.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,561.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45069115201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	422.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,412.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	64.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	21.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	60.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	4.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	20.227
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.309
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	21.764
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	20.239
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.068
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.324
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.466
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.040
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.393
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.474
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.387