

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

|                        |                                   |                            |                 |             |
|------------------------|-----------------------------------|----------------------------|-----------------|-------------|
| Letting:               | CT260225                          | Call Order: 010            | Proposal: T3928 | District:03 |
| Counties:              | BAY                               |                            |                 |             |
| Road Name:             | SCOTTS FERRY RD                   |                            |                 |             |
| Limits:                | OVER BEAR CREEK, BRIDGE NO 464419 |                            |                 |             |
| Project(s):            | 43938015201(*)                    | Federal Aid No:            | D325023B        |             |
| Total Roadway Length:  | 0.369 Miles                       | Contract Days:             | 610             |             |
| Total Bridge Length:   | 0.053 Miles                       | Letting Date:              | 02/25/26        |             |
| Total Proposal Length: | 0.422 Miles                       | Contract Execution Days:   | 10              |             |
|                        |                                   | Special Start Date:        | N/A             |             |
|                        |                                   | Aquis/Flexible Start Time: | 30 Days         |             |

Proposal Budget Estimate: \$8,819,289.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of replacing the existing low-level bridge including piles, approach slabs and slope protection at existing Scott's Ferry Road over Bear Creek, Bridge No. 464419, constructing a new bridge, Bridge No. 464169, with roadway approach reconstruction using asphalt pavement, shoulder gutter, and guardrail. All work to be done in Bay County.

**Call Order: 010 Proposal: T3928**

| ALT                            | Item        | Description                                                                        | Unit | Quantity    |
|--------------------------------|-------------|------------------------------------------------------------------------------------|------|-------------|
| <b>Section 0001 Structures</b> |             |                                                                                    |      |             |
|                                | 0110- 3-    | REMOVAL OF EXISTING STRUCTURES/BRIDGES (43938015201)                               | LS   | 1.000       |
|                                | 0400- 2- 4  | CONC CLASS II, BRIDGE SUPERSTRUCTURE                                               | CY   | 508.200     |
|                                | 0400- 2- 10 | CONCRETE CLASS II, APPROACH SLABS                                                  | CY   | 76.800      |
|                                | 0400- 4- 5  | CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE                                             | CY   | 121.400     |
|                                | 0400- 7- 1  | BRIDGE DECK GROOVING                                                               | SY   | 947.000     |
|                                | 0400- 9- 1  | BRIDGE DECK PLANING                                                                | SY   | 947.000     |
|                                | 0400-148-   | PLAIN NEOPRENE BEARING PADS                                                        | CF   | 18.000      |
|                                | 0415- 1- 4  | REINFORCING STEEL - BRIDGE SUPERSTRUCTURE                                          | LB   | 157,752.000 |
|                                | 0415- 1- 5  | REINFORCING STEEL- BRIDGE SUBSTRUCTURE                                             | LB   | 19,183.000  |
|                                | 0415- 1- 9  | REINFORCING STEEL- APPROACH SLABS                                                  | LB   | 14,244.000  |
|                                | 0415- 2- 5  | STAINLESS REINFORCING STEEL, SUBSTRUCTURE                                          | LB   | 216.000     |
|                                | 0455- 20- 1 | PILE INSPECTION, DRIVEN PILE                                                       | EA   | 36.000      |
|                                | 0455- 34- 5 | PRESTRESSED CONCRETE PILING, 24" SQ                                                | LF   | 2,543.000   |
|                                | 0455-115-   | PILE REDRIVE                                                                       | EA   | 27.000      |
|                                | 0455-137-   | LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS                                  | EA   | 36.000      |
|                                | 0455-143- 5 | TEST PILES-PRESTRESSED CONCRETE,24" SQ                                             | LF   | 983.000     |
|                                | 0458- 1- 11 | BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I<br>POURED JOINT WITH BACKER ROD | LF   | 63.000      |
|                                | 0521- 5- 13 | CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE                                 | LF   | 680.000     |
|                                | 0530- 1-100 | RIPRAP, SAND-CEMENT BAGS                                                           | CY   | 23.600      |
|                                | 0530- 3- 3  | RIPRAP- RUBBLE, BANK AND SHORE                                                     | TN   | 1,215.000   |
|                                | 0530- 74-   | BEDDING STONE                                                                      | TN   | 433.000     |
|                                | 0630- 2- 16 | CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS<br>AND TRAFFIC RAILINGS     | LF   | 2,040.000   |
|                                | 0635- 3- 13 | JUNCTION BOX, FURNISH & INSTALL, EMBEDDED                                          | EA   | 4.000       |

**Call Order: 010 Proposal: T3928**

| ALT                         | Item         | Description                                                    | Unit | Quantity   |
|-----------------------------|--------------|----------------------------------------------------------------|------|------------|
| <b>Section 0002 Roadway</b> |              |                                                                |      |            |
|                             | 0101- 1-     | MOBILIZATION (43938015201)                                     | LS   | 1.000      |
|                             | 0102- 1-     | MAINTENANCE OF TRAFFIC (43938015201)                           | LS   | 1.000      |
|                             | 0102- 2-200  | SPECIAL DETOUR- TEMPORARY PAVEMENT (43938015201)               | LS   | 1.000      |
|                             | 0102- 2-300  | SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43938015201)         | LS   | 1.000      |
|                             | 0102- 2-400  | SPECIAL DETOUR- TEMPORARY BRIDGE (43938015201)                 | LS   | 1.000      |
|                             | 0102- 60-    | WORK ZONE SIGN                                                 | ED   | 10,820.000 |
|                             | 0102- 71- 13 | TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE                  | LF   | 280.000    |
|                             | 0102- 73-    | TEMPORARY GUARDRAIL                                            | LF   | 3,395.000  |
|                             | 0102- 74- 1  | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD         | ED   | 8,480.000  |
|                             | 0102- 99-    | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY                    | ED   | 1,220.000  |
|                             | 0102-115-    | TYPE III BARRICADE                                             | ED   | 2,240.000  |
|                             | 0104- 1-     | ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS          | SY   | 142.000    |
|                             | 0104- 10- 3  | SEDIMENT BARRIER                                               | LF   | 3,096.000  |
|                             | 0104- 11-    | FLOATING TURBIDITY BARRIER                                     | LF   | 224.000    |
|                             | 0104- 12-    | STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC                 | LF   | 1,165.000  |
|                             | 0104- 15-    | SOIL TRACKING PREVENTION DEVICE                                | EA   | 2.000      |
|                             | 0110- 1- 1   | CLEARING & GRUBBING (43938015201)                              | LS   | 1.000      |
|                             | 0110- 4- 10  | REMOVAL OF EXISTING CONCRETE                                   | SY   | 575.000    |
|                             | 0120- 1-     | REGULAR EXCAVATION                                             | CY   | 6,878.700  |
|                             | 0120- 6-     | EMBANKMENT                                                     | CY   | 7,008.600  |
|                             | 0160- 4-     | TYPE B STABILIZATION                                           | SY   | 6,667.000  |
|                             | 0285-701-    | OPTIONAL BASE, BASE GROUP 01                                   | SY   | 244.000    |
|                             | 0285-706-    | OPTIONAL BASE, BASE GROUP 06                                   | SY   | 4,104.000  |
|                             | 0327- 70- 6  | MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH            | SY   | 815.000    |
|                             | 0334- 1- 52  | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22               | TN   | 379.800    |
|                             | 0337- 7- 81  | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22 | TN   | 419.200    |
|                             | 0339- 1-     | MISCELLANEOUS ASPHALT PAVEMENT                                 | TN   | 30.700     |
|                             | 0425- 1-701  | INLETS, GUTTER, TYPE S, <10'                                   | EA   | 6.000      |
|                             | 0430-175-118 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD                | LF   | 175.000    |
|                             | 0430-611-225 | U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:3 SLOPE, 18"PIPE  | EA   | 1.000      |
|                             | 0430-611-325 | U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE  | EA   | 1.000      |
|                             | 0520- 6-     | SHOULDER GUTTER- CONCRETE                                      | LF   | 589.000    |
|                             | 0530- 3- 4   | RIPRAP, RUBBLE, F&I, DITCH LINING                              | TN   | 28.100     |
|                             | 0530- 74-    | BEDDING STONE                                                  | TN   | 13.300     |
|                             | 0536- 1- 1   | GUARDRAIL -ROADWAY, GENERAL TL-3                               | LF   | 961.000    |
|                             | 0536- 73-    | GUARDRAIL REMOVAL                                              | LF   | 112.000    |
|                             | 0536- 85- 20 | GUARDRAIL END TREATMENT- TRAILING ANCHORAGE                    | EA   | 2.000      |
|                             | 0536- 85- 24 | GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL            | EA   | 2.000      |
|                             | 0550- 10-241 | FENCING, TYPE B, 7.1-8.0', WITH BARBED WIRE ATTACHMENT         | LF   | 676.000    |
|                             | 0570- 1- 2   | PERFORMANCE TURF, SOD                                          | SY   | 26,892.000 |
|                             | 0706- 1- 3   | RAISED PAVEMENT MARKER, TYPE B                                 | EA   | 1,215.000  |
|                             | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"          | GM   | 0.723      |
|                             | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"         | GM   | 0.723      |

**Call Order: 010 Proposal: T3928**

| ALT                         | Item         | Description                                                           | Unit | Quantity |
|-----------------------------|--------------|-----------------------------------------------------------------------|------|----------|
| <b>Section 0003 Signing</b> |              |                                                                       |      |          |
|                             | 0700- 1-111  | SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF | EA   | 2.000    |
|                             | 0700- 1-600  | SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE                            | EA   | 5.000    |
|                             | 0706- 1- 3   | RAISED PAVEMENT MARKER, TYPE B                                        | EA   | 112.000  |
|                             | 0710- 90-    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43938015201)                | LS   | 1.000    |
|                             | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"              | GM   | 0.737    |
|                             | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"             | GM   | 0.737    |
|                             | 0713-103-101 | PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES                 | GM   | 0.106    |
|                             | 0713-103-201 | PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES                | GM   | 0.106    |