

Call Order: 007 Proposal: T1928

ALT	Item	Description	Unit	Quantity
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,153.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1.400
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	177.600
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	43.300
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,381.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	26.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,147.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	2,116.000
	0527- 2-	DETECTABLE WARNINGS	SF	160.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,002.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44653515201)	LS	1.000
Section 0002 Signing				
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	8.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	3.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	16.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44653515201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	763.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	149.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 12-123	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 12" FOR CROSS WALK OR ROUNDABOUT	LF	716.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,041.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.040
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.062
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	78.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	443.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	20.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	7.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	4.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	18.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	7.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	7.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	2.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	2.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	2.000