

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251029	Call Order: 001	Proposal: T4729	District:04
Counties:	INDIAN RIVER			
Road Name:	SR A1A (JIMMY BUFFETT MEMORIAL HWY) OVER SEBASTIAN INLET			
Limits:	88070000			
Project(s):	44561815201(*)	Federal Aid No: D424104B		
Total Roadway Length:	1.465 Miles	Contract Days:	1715	
Total Bridge Length:	0.292 Miles	Letting Date:	10/29/25	
Total Proposal Length:	1.757 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$111,723,269.00			
Please read the full advertisement				
Description:	Bonus/Incentive-Disincentive			

Florida Department of Transportation

Bid Solicitation Notice and Approximate Quantities

The Improvements under this Contract consist of, but are not limited to, MOT (standard, special detour, traffic control officer, barrier, crash cushion, PCMS, barricade, removable tape), protections (sediment, turbidity, soil tracking), bridge replacement (removal of existing Bridge No. 880005, construction of new Bridge No. 880007, deck grooving and planning, expansion joint, bearing pads, prestressed beam), reef establishment, earthwork (excavation, embankment), reinforcing steel (retaining wall, superstructure, substructure, approach slab), reinforcing bars (fiber polymer), concrete (removal, steps, seal, approach slab, superstructure, substructure, mass, railing, parapet, barrier, shoulder barrier, coating, gravity wall, curb, curb and gutter, end wall, sidewalk, driveway, ditch pavement, bumper guards), piling (preformed holes, splice, inspection, prestressed, steel, steel sheet, polyethylene sheet, soldier wall, test piles, redrive), retaining wall (permanent, temporary), asphalt (milling, resurfacing, miscellaneous), fender system, navigation lights (system, solar), aluminum (ped/bike rail, pole F&I, pole remove), crash cushion, fence (standard, gate), riprap (rubble), bedding stone, gabion (mattress), monitor structures (inspection, settlement, vibration), drainage (inlets, manholes, pipe culvert, pipe fill/plug, French drain), conduit (trench, embedded), manatee grate, traffic monitoring site (cabinet, modem, sensor, solar power, surge suppressor), pavement markings (rumble strip, RPM, thermoplastic, painted, keyhole bike lane, permanent tape), signing (single-column, multi-column, sign strip), lighting (bollards, conductors luminaire, luminaire and light pole removal), box (pull/splice, junction), electric service (overhead power, wire, disconnect, load center), and sod along State Road A1A (Jimmy Buffett Memorial Highway) over Sebastian Inlet, for 1.098 miles, in Sebastian Inlet State Park, and in unincorporated portions of, Indian River County and Brevard County.

For projects in excess of \$50 million, in addition to meeting all other qualification requirements of Section 337.14, Florida Statutes, and Rule Chapter 14-22, Florida Administrative Code, any Contractor who is not prequalified and in good standing with the Department as of January 1, 2019, must submit evidence which demonstrates satisfactory completion of at least two projects, each in excess of \$15 million, for the Florida Department of Transportation or for any other state department of transportation. Acceptability of the evidence related to the two projects is at the sole discretion of the Department.

THERE WILL BE A MANDATORY PRE-BID MEETING FOR THIS PROJECT AT 10:30 AM EST ON WEDNESDAY, SEPTEMBER 23, 2025, AT THE FLORIDA DEPARTMENT OF TRANSPORTATION, DISTRICT 4 RICK CHESSER AUDITORIUM, 3400 W COMMERCIAL BLVD, FT. LAUDERDALE, FL 33309. IF YOU HAVE ANY QUESTIONS CONCERNING THIS MATTER, PLEASE CONTACT MARGARET SIMPKINS AT (954) 777-4612.

THIS PRE-BID MEETING IS MANDATORY BECAUSE OF THE COMPLEXITY OF THE PROJECT. ONLY PLANS AND SPECIFICATIONS WILL BE AVAILABLE PRIOR TO THE PRE-BID MEETING. THE PROSPECTIVE BIDDER SHALL BE PREQUALIFIED ACCORDING TO THE REQUIREMENTS OF FDOT RULE CHAPTER 14-22 AND SECTION 2-1 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

PROPOSALS (BIDDING DOCUMENTS) WILL BE ISSUED ONLY TO THE PROSPECTIVE BIDDERS WHO HAVE ATTENDED THE PRE-BID MEETING AND MET THE QUALIFICATIONS FOR THIS PROJECT.

PROSPECTIVE BIDDERS ORDERING BID DOCUMENTS PRIOR TO THE PRE-BID MEETING WILL BE GIVEN ACCESS TO DOWNLOAD THE BID DOCUMENTS WITHIN 24 HOURS AFTER THE PRE-BID MEETING. THOSE PROSPECTIVE BIDDERS ORDERING THE DOCUMENTS AFTER THE PRE-BID MEETING WILL NEED TO CONTACT THE OFFICE ADVERTISING THE PROJECT TO CONFIRM ATTENDANCE AND RECEIVE ACCESS TO DOWNLOAD THE BID DOCUMENTS. PLEASE CONTACT THE OFFICE AT LEAST TWO WORKING DAYS PRIOR TO THE DEADLINE FOR OBTAINING BID DOCUMENTS TO ALLOW TIME FOR PROCESSING.

Call Order: 001 Proposal: T4729

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44561815201)	LS	1.000
	0400- 0- 13	CONCRETE CLASS NS, STEPS	CY	30.000
	0400- 1- 30	CONCRETE, CLASS I (SEAL)	CY	98.100
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	182.500
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	3,283.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	239.100
	0400- 4- 11	CONC CLASS IV, RETAINING WALLS	CY	273.000
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	3,498.800
	0400- 7- 1	BRIDGE DECK GROOVING	SY	8,419.000

Call Order: 001 Proposal: T4729

ALT	Item	Description	Unit	Quantity
	0400- 9- 1	BRIDGE DECK PLANING	SY	8,419.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	81,790.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	78.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	8.200
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	49,217.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	833,580.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	968,613.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	35,550.000
	0415- 10- 4	FIBER REINFORCED POLYMER BARS, #4 BAR	LF	6,513.000
	0415- 10- 5	FIBER REINFORCED POLYMER BARS, #5 BAR	LF	31,727.000
	0450- 2- 96	PREST BEAMS: FLORIDA-I BEAM 96"	LF	11,179.000
	0450- 8- 72	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 18" CFRP/SS, WIDTH 52-54"	LF	1,224.000
	0455- 15- 13	PREFORMED PILE HOLES, 22" TO 26" DRILL/PUNCH SIZE	LF	2,690.000
	0455- 15- 14	PREFORMED PILE HOLES, 24" TO 29" DRILL/PUNCH SIZE	LF	594.000
	0455- 15- 16	PREFORMED PILE HOLES, 36" TO 43" DRILL/PUNCH SIZE	LF	10,714.000
	0455- 15- 24	PREFORMED PILE HOLES CASING, 24" TO 29" DRILL/PUNCH SIZE	LF	714.000
	0455- 15- 26	PREFORMED PILE HOLES CASING, 36" TO 43" DRILL/PUNCH SIZE	LF	10,811.000
	0455- 17-124	PRE-PLANNED PILE SPLICE, CONCRETE SQUARE, 24"	EA	59.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	221.000
	0455- 34- 2	PRESTRESSED CONCRETE PILING, 14" SQ.	LF	13,359.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	27,870.000
	0455- 34- 23	PRESTRESSED CONCRETE PILING, 18" SQ W/FRP OR STAINLESS STEEL STRAND AND REINFORCING	LF	890.000
	0455- 35- 5	STEEL PILING, HP 14 X 73	LF	3,894.000
	0455-115-	PILE REDRIVE	EA	126.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	14,100.000
	0455-133- 10	SOLDIER PILE WALL, TEMPORARY-CRITICAL, STEEL H-PILES WITH TIMBER LAGGING	SF	15,003.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	231.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	32.000
	0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	1,510.000
	0455-143- 23	TEST PILES-PRESTRESSED CONCRETE,18" SQ W/ FRP OR STAINLESS STEEL STRAND AND REINFORCING	LF	520.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	60.000
	0458- 1- 12	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I STRIP SEAL	LF	293.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	339.000
	0471- 1- 1	FENDER SYSTEM,PLASTIC MARINE LUMBER,REINFORCED	MB	30.800
	0471- 1- 2	FENDER SYSTEM,PLASTIC MARINE LUMBER, NON-REINFORCED	MB	11.400
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (44561815201)	LS	1.000
	0510- 1- 1	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM, SOLAR (44561815201)	LS	1.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	913.000
	0515- 2-703	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM, MODIFIED, 30" TYPE 1	LF	3,254.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	3,218.000

Call Order: 001 Proposal: T4729

ALT	Item	Description	Unit	Quantity
	0521- 6- 56	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, MODIFIED, 18" HEIGHT	LF	3,254.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,435.400
	0530- 5- 12	GABION, MATTRESS 1 FOOT AND GREATER THICKNESS	SY	2,945.000
	0530- 74-	BEDDING STONE	TN	533.800
	0550- 73-100	FLIGHT DIVERTERS	EA	122.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	15,665.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	228.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44561815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44561815201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44561815201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44561815201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44561815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	73,008.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	6,000.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	4,296.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	5,892.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	2,028.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	380,312.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	550,499.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	6.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	3,430.000
	0102-115-	TYPE III BARRICADE	ED	12,960.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.584
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.584
	0104- 10- 3	SEDIMENT BARRIER	LF	15,137.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	2,387.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	21,656.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	5.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	78.000
	0107- 1-	LITTER REMOVAL	AC	522.690
	0107- 2-	MOWING	AC	405.840
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44561815201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44561815201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44561815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,590.000
	0110- 84-	TRANSPORT EXISTING MATERIAL FOR REEF ESTABLISHMENT (44561815201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	10,992.200
	0120- 6-	EMBANKMENT	CY	64,653.500
	0160- 4-	TYPE B STABILIZATION	SY	43,232.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	3,632.000

Call Order: 001 Proposal: T4729

ALT	Item	Description	Unit	Quantity
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	10,672.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	24,197.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,236.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	3,779.000
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	2,070.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	53.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	21.100
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	17.000
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	4.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	6.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	1.000
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	9.000
	0425- 1-921	INLETS, ADJACENT BARRIER, <=10'	EA	8.000
	0425- 1-922	INLETS, ADJACENT BARRIER, >10'	EA	2.000
	0425- 1-923	INLETS, ADJACENT BARRIER, J BOTTOM, < 10'	EA	14.000
	0425- 1-924	INLETS, ADJACENT BARRIER, J BOTTOM, >10'	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	15.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	4.000
	0425- 2- 75	MANHOLES, J-7, >10' CONTROL STRUCTURE	EA	2.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	3,948.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	2,937.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	75.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	192.000
	0430-524-112	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 15 DEGREES, ELLIPTICAL	EA	1.000
	0430-530-112	STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 15 DEGREES, ELLIPTICAL	EA	1.000
	0430-613-229	U-ENDWALL, WITH BAFFLES & GRATE, INDEX 261/430-011,1:3 SLOPE, 24 "PIPE	EA	1.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	5.600
	0430-886- 30	MANATEE GRATE FOR 30" PIPE, UNHINGED	EA	1.000
	0443- 70- 4	FRENCH DRAIN, 24"	LF	794.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	770.000
	0515- 2-703	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM, MODIFIED, 30" TYPE 1	LF	3,728.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	2,725.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	3,324.000
	0521- 6- 57	CONCRETE PARAPET, RETAINING WALL SYSTEM MOUNTED W/SIDEWALK, MODIFIED, 18" HEIGHT	LF	3,563.000
	0521- 6- 58	CONCRETE PARAPET, RETAINING WALL SYSTEM MOUNTED W/SIDEWALK, SPECIAL	LF	165.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	740.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	3,694.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	233.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	2,091.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	10.000

Call Order: 001 Proposal: T4729

ALT	Item	Description	Unit	Quantity
	0527- 2-	DETECTABLE WARNINGS	SF	200.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	741.300
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	2.000
	0530- 74-	BEDDING STONE	TN	277.400
	0542- 70-	BUMPER GUARDS, CONCRETE	EA	31.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	2.000
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	79,332.000
	0548- 13-	RETAINING WALL SYSTEM, TEMPORARY, EXCLUDING BARRIER	SF	33,400.000
	0550- 10-230	FENCING, TYPE B, 6.1-7.0', STANDARD	LF	564.000
	0550- 60-223	FENCE GATE, TYPE B, DOUBLE, 12.1-18.0' OPENING	EA	1.000
	0550- 60-422	FENCE GATE, WOOD, DOUBLE, 6.1-12.0 FOOT OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	34,416.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	16.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	18,029.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	253.000
	0646- 2-120	ALUMINUM POLE- INDEX 695-001, FURNISH & INSTALL, 20'	EA	1.000
	0646- 2-600	ALUMINUM POLE- INDEX 695-001, REMOVE	EA	1.000
	0695- 7-133	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, POLE MOUNT	EA	1.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	1.000
	0695- 8- 11	TRAFFIC MONITORING SITE COMMUNICATIONS MODEM FURNISH & INSTALL	EA	1.000
	0695- 12- 1	TRAFFIC MONITORING SITE NON-MOTORIZED AXLE SENSOR, FURNISH & INSTALL	EA	1.000
	0695- 15- 1	TRAFFIC MONITORING SITE NON-MOTORIZED SOLAR POWER UNIT, FURNISH & INSTALL	EA	1.000
	0695- 16- 1	TRAFFIC MONITORING SITE SURGE SUPPRESSOR, FURNISH & INSTALL	EA	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.262
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	90.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.111
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	15.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.782
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	312.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.038
	0999- 16-	PARTNERING, DO NOT BID (44561815201)	LS	1.000
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	58.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44561815201)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	2.775

Call Order: 001 Proposal: T4729

ALT	Item	Description	Unit	Quantity
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	34.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	7.000
	0700- 1-211	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, LESS THAN 12 SF	EA	14.000
	0700- 1-212	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, 12.0-20.0 SF	EA	6.000
	0700- 1-311	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, LESS THAN 12 SF	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	48.000
	0700- 2-111	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	2.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	462.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44561815201)	LS	1.000
	0711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6" FOR PARKING SPACES	LF	6,230.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.248
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	14.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	71.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	452.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID, 6"	LF	388.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	535.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	256.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	4.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	4.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.648
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.114
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.185
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.170
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.585
	0714- 10-	GREEN-COLORED PAVEMENT MARKINGS, BIKE LANE	SF	1,402.000
Section 0004 Lighting				
	0519- 78-	BOLLARDS	EA	84.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,281.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	255.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	23.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	20.000

Call Order: 001 Proposal: T4729

ALT	Item	Description	Unit	Quantity
	0639- 1-111	ELECTRICAL POWER SERVICE, F&I, OVERHEAD, METER FURNISHED BY POWER COMPANY	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	71.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	3.000
	0639- 3- 12	ELECTRICAL SERVICE DISCONNECT, F&I, CABINET	EA	3.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	17,437.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	213.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	4.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	8.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	9.000