

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251029	Call Order: 014	Proposal: T5861	District:05
Counties:	VOLUSIA			
Road Name:	SR A1A (OCEAN SHORE BLVD)			
Limits:	FROM N OF ROBERTA RD TO FLAGLER CO LINE			
Project(s):	45094615201(*)	Federal Aid No:	D524048B	
Project(s):	45094615202	Federal Aid No:	N/A	
Total Roadway Length:	6.907 Miles	Contract Days:	550	
Total Bridge Length:	0.000 Miles	Letting Date:	10/29/25	
Total Proposal Length:	6.907 Miles	Contract Execution Days:	10	
		Special Start Date:	04/20/26	
		Aquis/Flexible Start Time:	N/A	
Proposal Budget Estimate:	\$16,708,687.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, drainage improvements, curb & gutter, bike path/ trail, sidewalk, signing and pavement marking on SR A1A from north of Roberta Road to the Flagler County Line, approximately 6.907 miles in Volusia County.

Call Order: 014 Proposal: T5861

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45094615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45094615201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (45094615201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (45094615201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	425.700
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45094615201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	240.000
	0102- 60-	WORK ZONE SIGN	ED	381,683.000
	0102- 61-	BUSINESS SIGN	EA	6.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	16,932.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	3,768.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	532,088.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	7,301,162.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	704.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	6,942.000
	0102-115-	TYPE III BARRICADE	ED	46,535.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	14.000
	0102-913- 23	REMOVABLE TAPE, WHITE, 24" STOP BAR	LF	872.000
	0102-913- 24	REMOVABLE TAPE, WHITE, 12" CROSSWALK	LF	6,896.000
	0104- 10- 3	SEDIMENT BARRIER	LF	17,340.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000

Call Order: 014 Proposal: T5861

ALT	Item	Description	Unit	Quantity
	0104- 18-	INLET PROTECTION SYSTEM	EA	27.000
	0107- 1-	LITTER REMOVAL	AC	956.120
	0107- 2-	MOWING	AC	425.220
	0110- 1- 1	CLEARING & GRUBBING (45094615201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	10,412.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	7.000
	0120- 1-	REGULAR EXCAVATION	CY	3,522.400
	0120- 6-	EMBANKMENT	CY	6,374.300
	0160- 4-	TYPE B STABILIZATION	SY	3,432.000
	0285-708-	OPTIONAL BASE, BASE GROUP 08	SY	2,118.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	5,344.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	89,882.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	18,340.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	19,417.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	9,542.500
	0354- 1-102	PERVIOUS CONCRETE PAVEMENT, 6"	SY	1,274.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	86.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	6.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	13.000
	0425- 1-525	INLETS, DITCH BOTTOM, TYPE C, PARTIAL	EA	4.000
	0425- 1-565	INLETS, DITCH BOTTOM, TYPE F, PARTIAL	EA	6.000
	0425- 2- 73	MANHOLES, J-7, PARTIAL	EA	12.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	74.000
	0443- 70- 3	FRENCH DRAIN, 18"	LF	688.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	445.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	623.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	21,988.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	46.000
	0520- 2-100	CONCRETE CURB, RIBBON CURB	LF	2,909.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	282.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	22,779.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	356.000
	0527- 2-	DETECTABLE WARNINGS	SF	2,653.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	44,372.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	5,121.000
	0590- 70- 5	IRRIGATION SYSTEM- MODIFY EXISTING SYSTEM (45094615201)	LS	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,340.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	17.164
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	188.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	77.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.328

Call Order: 014 Proposal: T5861

ALT	Item	Description	Unit	Quantity
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	18.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	30.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	19.758
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	12.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	7.881
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	339.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	36.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	30.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	60.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	286.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	35.000
	0700-142-171	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/EDS AND BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	2.000
	0700-142-902	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, REMOVE - GROUND MOUNT	EA	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	123.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,965.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	10.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45094615201)	LS	1.000
	0711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6" FOR PARKING SPACES	LF	631.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,791.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	951.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.208
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	25.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,069.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID, 6"	LF	54.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,325.000
	0711- 14-760	THERMOPLASTIC, PREFORMED, MULTI COLOR, IN PAVEMENT WARNING	EA	36.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	14.113
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	9.256
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	2.759

Call Order: 014 Proposal: T5861

ALT	Item	Description	Unit	Quantity
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	53.000
Section 0003 Signalization				
	0654- 2- 22	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSEMBLY- BACK TO BACK	AS	2.000
	0654- 2- 28	MIDBLOCK CROSSWALK: REC RAPID FLASHING BEACON, FURNISH/INSTALL- SOLAR, SIGN ASSEMBLY- BACK-BACK ACCESSIBLE DETECTOR	AS	6.000
	0654- 2- 60	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, REMOVE COMPLETE SIGN ASSEMBLY	AS	2.000