

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250924	Call Order: 011	Proposal: T6592	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 886 (PORT BLVD)			
Limits:	FROM BISCAYNE BLVD TO PORT OF MIAMI			
Project(s):	44391315201(*)	Federal Aid No:	D625017B	
Project(s):	44391315202	Federal Aid No:	D625017B	
Total Roadway Length:	0.785 Miles	Contract Days:	270	
Total Bridge Length:	0.000 Miles	Letting Date:	09/24/25	
Total Proposal Length:	0.785 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$4,090,852.00			

Please read the full advertisement

Description: Incentive / Disincentive

THE IMPROVEMENTS UNDER THIS CONTRACT CONSIST OF RIGID PAVEMENT REHABILITATION ALONG SR 886/PORT BLVD FROM BISCAYNE BLVD TO PORT OF MIAMI IN MIAMI DADE-COUNTY.

Call Order: 011 Proposal: T6592

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44391315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44391315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,036.000
	0102- 60-	WORK ZONE SIGN	ED	20,565.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	365.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	193.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	104,670.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	31,267.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,125.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	658.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	810.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	810.000
	0102-115-	TYPE III BARRICADE	ED	4,095.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	11.000
	0107- 1-	LITTER REMOVAL	AC	40.660
	0107- 2-	MOWING	AC	40.660
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44391315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44391315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44391315202)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.020
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	3,300.000

Call Order: 011 Proposal: T6592

ALT	Item	Description	Unit	Quantity
	0110- 21-	TREE PROTECTION BARRIER	LF	149.000
	0110- 22-	TREE ROOT AND BRANCH PRUNING	EA	2.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44391315201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	59.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	59.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,522.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	6.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	212.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	2.200
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	23,252.000
	0350- 6-	CLEANING & SEALING RANDOM CRACKS- CONCRETE PAVEMENT	LF	48.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	14,430.000
	0353- 70-	CONCRETE PAVEMENT SLAB REPLACEMENT	CY	886.200
	0425- 5-	MANHOLE, ADJUST	EA	4.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	255.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	11.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	56.000
	0521- 72-108	SHOULDER CONCRETE BARRIER, 32" F-SHAPE	LF	41.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	95.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	142.000
	0526- 1- 2	PAVERS, ARCHITECTURAL, SIDEWALK	SY	145.000
	0527- 2-	DETECTABLE WARNINGS	SF	145.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	81.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	81.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	4.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0544- 2- 1	CRASH CUSHION, TL-2, NARROW	EA	1.000
	0570- 1- 1	PERFORMANCE TURF	SY	44.000
	0590- 70- 5	IRRIGATION SYSTEM- MODIFY EXISTING SYSTEM (44391315202)	LS	1.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (44391315201)	LS	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,722.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.155
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.255
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.064
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.251
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44391315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44391315202)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	12.000

Call Order: 011 Proposal: T6592

ALT	Item	Description	Unit	Quantity
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	9.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-211	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, LESS THAN 12 SF	EA	3.000
	0700- 1-212	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	15.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-408	SIGN PANEL, INSTALL, 301-400 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	1.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	2.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	4.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	5.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	962.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44391315201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44391315202)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.216
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	180.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	633.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	47.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.033
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	7.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	228.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	293.000
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.089
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	10.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	15.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	92.000
	0711- 14-194	THERMOPLASTIC, PREFORMED, 12" WHITE WITH 4" OUTSIDE BLACK CONTRAST ON CONCRETE PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	949.000
	0711- 14-527	THERMOPLASTIC, PREFORMED, 24" WHITE WITH 4" BLACK CONTRAST FOR STOP LINE ON CONCRETE PAVEMENT, 32"	LF	322.000
	0711- 14-528	THERMOPLASTIC, PREFORMED, 12" WHITE WITH 4" BLACK CONTRAST FOR CROSSWALK ON CONCRETE PAVEMENT, 20"	LF	174.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.131

Call Order: 011 Proposal: T6592

ALT	Item	Description	Unit	Quantity
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.097
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.972
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.190
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	2.542
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.440
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	2.544
Section 0003 Lighting				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	12.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,473.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	270.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	31.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	1,160.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	600.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	1.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	1.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	6.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	3.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	3.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	1.000
Section 0005 Intelligent Transportation System				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000