

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250730	Call Order: 011	Proposal: T4674	District:04
Counties:	PALM BEACH			
Road Name:	SR 80 (SOUTHERN BLVD RAMPS)			
Limits:	AT SR 7 (US 441)			
Project(s):	43786815201(*)	Federal Aid No:	D424098B	
Total Roadway Length:	0.752 Miles	Contract Days:	428	
Total Bridge Length:	0.027 Miles	Letting Date:	07/30/25	
Total Proposal Length:	0.078 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days	
Proposal Budget Estimate:	\$10,065,316.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of, but are not limited to, MOT (standard, pedestrian/bicycle detour, traffic control officer, barrier, barricade, pedestrian LCD, arrow board, crash cushion, PCMS, signalization, traffic detection), environmental (sediment, turbidity, inlet protection, tree protection), monitor structures (inspection, settlement, vibration), excavation (regular, subsoil, channel), embankment, bridge (removal, widening, bearing pad, expansion joint, deck grooving/planning, coating, drainage), roadway (add lanes, widening), concrete (removal, superstructure, approach slab, substructure, revetment system, piling, bridge traffic railing, curb and gutter, traffic separator, shoulder barrier, sidewalk, driveways), steel (reinforcing), piles (inspection, prestressed, redrive, load testing, test piles), asphalt (milling, resurfacing, misc.), guardrail (removal, end treatment, transition, post, pipe rail), pavement markings (temporary tape, permanent tape, painted, RPM, thermoplastic, sign strip, detectable, bike lane), pavers (remove, reset), signing (single-column, panel, overhead static, illuminated), conduit (embedded, bridge mount, trench, bore), utilities (pull box, splice box, junction box), lighting (conductors, luminaires. Load center, high-mast pole, pole complete, cable distribution), ITS (documentation, location, CCTV camera), signalization (signal cable, fiber optic cable, aluminum pole, steel mast arm, mast arm removal, vehicular signal, pedestrian signal and detector, inductive loop, controller), ethernet, UPS, drainage (inlets, manholes, culvert, MES), irrigation modifications, tree/palm relocations, and sod along State Road 80 (Southern Boulevard) Ramps and State Road 7 (US-441) for 0.779 miles in Palm Beach County.

Call Order: 011 Proposal: T4674

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43786815201)	LS	1.000
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	147.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	36.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	16.000
	0400- 7- 1	BRIDGE DECK GROOVING	SY	135.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	135.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	1,500.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	0.600
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	22,170.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	3,970.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	4,700.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	9.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	740.000
	0455-115-	PILE REDRIVE	EA	2.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	2.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	170.000

Call Order: 011 Proposal: T4674

ALT	Item	Description	Unit	Quantity
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	28.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	9.000
	0506- 2-	BRIDGE DRAINAGE PIPE	LF	173.000
	0506- 3-	BRIDGE DRAINS	EA	6.000
	0515- 4- 2	BULLET RAIL, DOUBLE RAIL	LF	211.000
	0521- 5- 4	CONCRETE TRAFFIC RAILING- BRIDGE, 32" VERTICAL FACE	LF	211.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	472.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	240.000
	0635- 3- 11	JUNCTION BOX, FURNISH & INSTALL, AERIAL	EA	2.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	3.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	2.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43786815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43786815201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43786815201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (43786815201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	416.000
	0102- 60-	WORK ZONE SIGN	ED	18,364.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,452.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	480.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	2,292.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	44,484.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	228,552.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,043.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,691.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	537.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	537.000
	0102-115-	TYPE III BARRICADE	ED	116.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.759
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.759
	0102-913- 29	REMOVABLE TAPE, WHITE, MESSAGE, SYMBOL OR ARROW	EA	14.000
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.128
	0104- 10- 3	SEDIMENT BARRIER	LF	1,441.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	263.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	34.000
	0107- 1-	LITTER REMOVAL	AC	75.450
	0107- 2-	MOWING	AC	75.450
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43786815201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43786815201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43786815201)	LS	1.000

Call Order: 011 Proposal: T4674

ALT	Item	Description	Unit	Quantity
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,371.000
	0110- 21-	TREE PROTECTION BARRIER	LF	512.000
	0120- 1-	REGULAR EXCAVATION	CY	2,647.700
	0120- 4-	SUBSOIL EXCAVATION	CY	240.000
	0120- 5-	CHANNEL EXCAVATION	CY	328.000
	0120- 6-	EMBANKMENT	CY	837.500
	0160- 4-	TYPE B STABILIZATION	SY	5,507.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	4,105.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	472.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	31,563.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,095.200
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	3,193.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	38.300
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	6.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	2.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	1.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 2- 73	MANHOLES, J-7, PARTIAL	EA	3.000
	0425- 5-	MANHOLE, ADJUST	EA	5.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	632.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	1.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	398.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	3,127.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	286.000
	0521- 72- 60	SHOULDER CONCRETE BARRIER, 38" WALL SHIELDING BARRIER	LF	200.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	884.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	288.000
	0526- 1-101	PAVERS, ARCHITECTURAL, REMOVE EXISTING AND REINSTALL	SY	54.000
	0527- 2-	DETECTABLE WARNINGS	SF	123.000
	0530- 4- 6	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 6"	SY	234.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	944.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	61.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	11.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	1.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	2.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	1.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 1	PERFORMANCE TURF	SY	1,313.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,334.000

Call Order: 011 Proposal: T4674

ALT	Item	Description	Unit	Quantity
	0590- 70- 5	IRRIGATION SYSTEM- MODIFY EXISTING SYSTEM (43786815201)	LS	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,428.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.514
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.078
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,674.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	60.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	316.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.394
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.025
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	16.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	91.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.893
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.078
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	80.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.673
	0999- 16-	PARTNERING, DO NOT BID (43786815201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43786815201)	LS	1.000
Section 0003 Signing				
	0649- 21-142	STEEL MAST ARM ASSEMBLY, SPECIAL DESIGN, FURNISH AND INSTALL, SINGLE ARM 96'	EA	1.000
	0649- 21-143	STEEL MAST ARM ASSEMBLY, SPECIAL DESIGN, FURNISH AND INSTALL, SINGLE ARM 88'	EA	1.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	23.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	30.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	14.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	8.000
	0700- 4-611	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, CANTILEVER	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,476.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	11.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43786815201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.006

Call Order: 011 Proposal: T4674

ALT	Item	Description	Unit	Quantity
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,255.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	323.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	383.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.727
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	18.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	149.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	226.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.050
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,166.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	22.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	50.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.137
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.134
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.991
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.784
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.082
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.275
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.086
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.068
	0714- 10-	GREEN-COLORED PAVEMENT MARKINGS, BIKE LANE	SF	3,340.000
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,300.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	315.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	28.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	1,800.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	6,650.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	11,695.000
	0715- 5- 31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	4.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	1.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	12.000
	0715- 19- 62	HIGH MAST LIGHT POLE, SHALLOW FOUNDATION REMOVAL	EA	1.000
	0715- 21- 2	LIGHTING REPAIRS AND RETROFITS, LED RETROFIT KIT FOR EXISTING LUMINAIRE	EA	11.000
	0715- 61-242	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 12' ARM LENGTH	EA	4.000
	0715- 61-342	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 12' ARM LENGTH	EA	15.000

Call Order: 011 Proposal: T4674

ALT	Item	Description	Unit	Quantity
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	8.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	30.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	12.000
Section 0005 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	719.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	694.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	47.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-420	ELECTRICAL POWER SERVICE, RELOCATE, UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	200.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	200.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	12.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	13.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0649- 21- 19	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 70'-60'	EA	2.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	4.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	44.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	9.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	12.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	11.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	3.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	30.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	12.000
	0670- 5-162	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA W/STANDARD LOCK, 2 PREEMPTION	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0685- 2- 3	REMOTE POWER MANAGEMENT UNIT- RPMU, INSTALL	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	6.000
	0700- 4-640	OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT	EA	2.000

Call Order: 011 Proposal: T4674

ALT	Item	Description	Unit	Quantity
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	8.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	2.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	2.000
Section 0006 Landscape / Peripheral				
	0581- 1- 7	RELOCATE TREES AND PALMS,PALMS, <14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	2.000
	0581- 1- 8	RELOCATE TREES AND PALMS, >=14' OF CLEAR TRUNK, SABAL PALM ONLY	EA	43.000
	0581- 1-271	RELOCATE TREES AND PALMS, OTHER PALMS, <10.0" DBH, <14.0' OF CLEAR TRUNK	EA	5.000
	0581- 1-272	RELOCATE TREES AND PALMS, OTHER PALMS, <10.0" DBH, 14.0' OR GREATER OF CLEAR TRUNK	EA	31.000
Section 0007 Intelligent Transportation System				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.779
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	1.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	266.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	50.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	200.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	250.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	880.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	96.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	12.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	1.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	428.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	5.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	1.000
	0682- 1-163	ITS CCTV CAMERA, PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0685- 2- 3	REMOTE POWER MANAGEMENT UNIT- RPMU, INSTALL	EA	1.000