

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250827	Call Order: 012	Proposal: T6609	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 986 (SUNSET DR) AND SR 94 (KENDALL DR)			
Limits:	AT SW 72ND ST, AT SR 826 SB OFF-RAMP AND AT SW 157TH AVE			
Project(s):	44936715201	Federal Aid No:	D625015B	
Project(s):	44936715601	Federal Aid No:	D625015B	
Project(s):	44936915201(*)	Federal Aid No:	D625016B	
Total Roadway Length:	0.387Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	08/27/25	
Total Proposal Length:	0.387 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$1,898,450.00			

Please read the full advertisement

Description:

THE IMPROVEMENTS UNDER THIS CONTRACT CONSIST OF INTERSECTION IMPROVEMENT ALONG STATE ROAD 986/SUNSET DRIVE AND STATE ROAD 826 SOUTH BOUND OFF RAMP AND SAFETY PROJECT ALONG STATE ROAD 94/KENDALL DRIVE AND SW 157 AVENUE IN MIAMI-DADE COUNTY.

Call Order: 012 Proposal: T6609

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44936715201)	LS	1.000
	0101- 1-	MOBILIZATION (44936915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44936715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44936915201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	100.000
	0102- 60-	WORK ZONE SIGN	ED	19,800.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	44,280.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	4,050.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	720.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	776.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	540.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	540.000
	0102-115-	TYPE III BARRICADE	ED	1,440.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	19.000
	0107- 1-	LITTER REMOVAL	AC	7.790
	0107- 2-	MOWING	AC	2.390
	0110- 1- 1	CLEARING & GRUBBING (44936915201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	352.000
	0160- 4-	TYPE B STABILIZATION	SY	24.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	24.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	11,279.000

Call Order: 012 Proposal: T6609

ALT	Item	Description	Unit	Quantity
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	2,192.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	4.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	87.900
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	775.400
	0425- 5-	MANHOLE, ADJUST	EA	8.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	295.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	139.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	190.000
	0527- 2-	DETECTABLE WARNINGS	SF	136.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	15.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (44936715201)	LS	1.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (44936915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44936715201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44936915201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	7.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-212	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-312	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	317.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	39.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44936715201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44936915201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.031
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	919.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	108.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	273.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.022
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	27.000

Call Order: 012 Proposal: T6609

ALT	Item	Description	Unit	Quantity
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.005
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	777.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.250
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.058
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.693
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.482
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.383
Section 0003 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,985.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	2.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	180.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	68.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	2.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	833.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	773.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	7.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	5.000
	0649- 21- 7	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 50'-30'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	6.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	1.000
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	13.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	10.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	8.000

Call Order: 012 Proposal: T6609

ALT	Item	Description	Unit	Quantity
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	5.000
	0660- 1-600	LOOP DETECTOR INDUCTIVE, REMOVE- CABINET TO REMAIN	EA	6.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	5.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	4.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	4.000
	0660- 4- 60	VEHICLE DETECTION SYSTEM- VIDEO, REMOVE	EA	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	16.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	4.000
	0670- 5-180	TRAFFIC CONTROLLER ASSEMBLY, F&I, CALTRANS W/STANDARD LOCK	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0684- 8- 1	CELLULAR MODEM, FURNISH AND INSTALL	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	2.000
Section 0004 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44936715601)	LS	1.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	7.000