



**Call Order: 012 Proposal: T7576**

ALT	Item	Description	Unit	Quantity
	0120- 1-	REGULAR EXCAVATION	CY	642.900
	0120- 6-	EMBANKMENT	CY	623.000
	0327- 70- 16	MILLING EXISTING ASPHALT PAVEMENT, 1/2" AVG DEPTH	SY	25,861.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	2,133.500
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	13.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	13.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	4.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	2.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	1,312.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	251.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	8.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	59.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	1.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	2,550.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	3,954.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	215.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,706.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	132.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	1,403.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	369.000
	0527- 2-	DETECTABLE WARNINGS	SF	76.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	39.100
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,370.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	148.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.880
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44110515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44110515202)	LS	1.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (44110515601)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	7.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	34.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	16.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	652.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	107.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44110515201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44110515202)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	365.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	82.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	9.000

**Call Order: 012 Proposal: T7576**

ALT	Item	Description	Unit	Quantity
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.310
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	201.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.762
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.746
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.454
<b>Section 0003 Utilities</b>				
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	13.000
	0425- 6-	VALVE BOXES, ADJUST	EA	8.000
	1050- 16-003	UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	LF	23.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	40.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	60.000
	1050- 31-212	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 12"	LF	70.000
	1055- 31-112	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, ELBOW, 12"	EA	16.000
	1055- 31-512	UTILITY FITTINGS FOR PVC PIPE, FURNISH AND INSTALL, CAP/PLUG, 12"	EA	4.000
	1080- 21-112	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 12"	EA	4.000
	1080- 23-112	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 12"	EA	4.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	4.000
	1080- 27-112	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 12"	EA	4.000
	1080- 29-106	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 6"	EA	14.000
	1080- 29-112	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 12"	EA	56.000