

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261202	Call Order: 013	Proposal: T3A41	District:03
Counties:	LEON			
Road Name:	SR 63 (US 27 / MONROE ST)			
Limits:	FROM SR 263 (CAPITAL CIR) TO N OF JOHN KNOX RD			
Project(s):	45293915201(*)	Federal Aid No:	D326038B	
Project(s):	45293915202	Federal Aid No:	N/A	
Project(s):	45293915203	Federal Aid No:	N/A	
Project(s):	45293915204	Federal Aid No:	N/A	
Total Roadway Length:	5.980 Miles	Contract Days:	435	
Total Bridge Length:	0.070 Miles	Letting Date:	12/02/26	
Total Proposal Length:	6.050 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days Flexible	
Proposal Budget Estimate:	\$13,696,782.00			

Please read the full advertisement

Description:

The improvements under this Contract (FPID 452939-1-52-01) consist of resurfacing SR 63 (US 27/Monroe St) from SR 263 (Capital Cir) to N of John Knox Rd in Leon County. This project will primarily consist of milling and resurfacing the existing travel lanes, auxiliary lanes, median crossovers, and paved shoulders. In addition to the resurfacing, the scope of services for this project includes median access changes, sidewalk additions, signalization improvements, and addresses design deficiencies such as deficient sidewalks, non-compliant curb ramps, clear space requirements, and pedestrian signal features. The project will include restriping of existing Bridge #550068 and Bridge #550085 over SR 8 (I-10). There are no proposed improvements to Bridge Culvert #550003 over Meginnis Arm. Utility Work by Highway Contractor will include adjustments to manholes and valves owned by the City of Tallahassee Water and Sewer under FPID 452939-1-52-02, City of Tallahassee Power under FPID 452939-1-52-03, and CenturyLink aka Lumen (Local) under FPID 452939-1-52-04.

Call Order: 013 Proposal: T3A41

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45293915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45293915201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	816.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,000.000
	0102- 60-	WORK ZONE SIGN	ED	66,106.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	80,914.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	900.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	580.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	6,021.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,506.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	4,785.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	4,785.000
	0102-115-	TYPE III BARRICADE	ED	8.000
	0104- 10- 3	SEDIMENT BARRIER	LF	955.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	209.000

Call Order: 013 Proposal: T3A41

ALT	Item	Description	Unit	Quantity
	0107- 1-	LITTER REMOVAL	AC	1,235.820
	0107- 2-	MOWING	AC	1,136.680
	0110- 1- 1	CLEARING & GRUBBING (45293915201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	783.000
	0110- 21-	TREE PROTECTION BARRIER	LF	5,296.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,335.200
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (45293915201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	999.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	69.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	57.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	139,651.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	58,294.000
	0327- 70- 13	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH	SY	39,374.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	71,991.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	26,871.400
	0337- 7- 27	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-7, PG 76-22	TN	5,812.600
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	13,567.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	24.200
	0425- 1-471	INLETS, CURB, TYPE 7, <10'	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	5.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	1.000
	0425- 4-	INLETS, ADJUST	EA	1.000
	0425- 7-	MANHOLE COVER- REPLACE	EA	1.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	2.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	379.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	207.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	63.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	2,835.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	649.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	43.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	341.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	137.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	397.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,527.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	700.000
	0536- 73-	GUARDRAIL REMOVAL	LF	528.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	24,943.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	18.611
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.466
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	10,755.000

Call Order: 013 Proposal: T3A41

ALT	Item	Description	Unit	Quantity
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	3,275.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	2,643.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	12.954
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.996
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	41.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	480.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	11.525
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	962.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.099
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.587
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45293915201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	208.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	30.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	25.000
	0700- 1-114	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1+ SF SHEETING AREA FOR BACK TO BACK SIGNS	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	9.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	90.000
	0700- 2-111	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	2.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	5.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	128.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	137.000
	0700-141-112	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, W/BEACON, 12-20 SF OF STATIC SIGN PANELS	EA	4.000
	0700-141-902	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, REMOVE - GROUND MOUNT	EA	4.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	26.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	91.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	7.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	6,021.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45293915201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	10,755.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	3,275.000

Call Order: 013 Proposal: T3A41

ALT	Item	Description	Unit	Quantity
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	2,643.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	2.996
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	41.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	480.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	962.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.587
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	4,568.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	137.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	137.000
	0711- 14-528	THERMOPLASTIC, PREFORMED, 12" WHITE WITH 4" BLACK CONTRAST FOR CROSSWALK ON CONCRETE PAVEMENT, 20"	LF	56.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	7.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	7.731
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.240
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	8.442
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	4.729
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	10.878
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	1.226
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.512
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	6.796
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.099
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	929.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.421
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.281
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.140
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.281
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,491.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	4,826.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	9.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	9.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	102.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	7.000

Call Order: 013 Proposal: T3A41

ALT	Item	Description	Unit	Quantity
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	36.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	3.000
	0649- 21- 14	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 60'-60'	EA	1.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	14.000
	0650- 1- 15	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 2-4 WAYS	AS	1.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	5.000
	0650- 1- 18	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION STRAIGHT, 1 WAY	AS	3.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	6.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	19.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	6.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	52.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	68.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	132.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	49.000
	0660- 6-422	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH RELOCATE, ABOVE GROUND EQUIPMENT	EA	1.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	59.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	47.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	3.000
Section 0004 Utilities				
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES (45293915202)	EA	17.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES (45293915203)	EA	6.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES (45293915204)	EA	3.000
	0425- 6-	VALVE BOXES, ADJUST	EA	47.000