

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251203	Call Order: 005	Proposal: T2A52	District:02
Counties:	SUWANNEE			
Road Name:	SR 8 (I-10)			
Limits:	FROM SR 10 (US 90) TO SR 51 (US 129)			
Project(s):	21356045201(*)	Federal Aid No:	D225023B	
Total Roadway Length:	9.141 Miles	Contract Days:	400	
Total Bridge Length:	0.013 Miles	Letting Date:	12/03/25	
Total Proposal Length:	9.271 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$25,092,654.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, base work, shoulder treatment, highway signing, guardrail, and other incidental construction on SR 8 (I-10) in Suwannee County from SR 10 (US 90) to SR 51 (US 129).

Call Order: 005 Proposal: T2A52

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	580.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	62.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (21356045201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21356045201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	2,400.000
	0102- 60-	WORK ZONE SIGN	ED	17,912.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	458.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	1,730.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	86,010.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	286.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	5.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,800.000
	0102-115-	TYPE III BARRICADE	ED	80.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	480.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	480.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	5.000
	0104- 10- 3	SEDIMENT BARRIER	LF	20,426.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	51.000
	0107- 1-	LITTER REMOVAL	AC	5,564.160
	0107- 2-	MOWING	AC	5,026.700
	0110- 1- 1	CLEARING & GRUBBING (21356045201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	5.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	355.400

Call Order: 005 Proposal: T2A52

ALT	Item	Description	Unit	Quantity
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (138 CY)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	8,620.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	911.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	380.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	167.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	6,555.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	193,174.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	13,795.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	1,491.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	5,221.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	264,930.000
	0327- 70- 28	MILLING EXISTING ASPHALT PAVEMENT, 6 3/4" AVG DEPTH	SY	4,027.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	16,886.900
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	4,776.300
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	51,583.300
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	11,576.700
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	6,347.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	231.600
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	3,151.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-002, APPROACH TL-3	EA	5.000
	0536- 73-	GUARDRAIL REMOVAL	LF	2,141.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	20.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	89,140.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	5,859.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	64.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	400.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	7,250.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	47.895
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	56.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	84.600
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	49.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	47.017
	0924-102-	WORK ZONE COLLISION DETECTION AND AVOIDANCE SYSTEM FOR PAVING OPERATIONS (21356045201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21356045201)	LS	1.000
Section 0003 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	35.304

Call Order: 005 Proposal: T2A52

ALT	Item	Description	Unit	Quantity
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	1.807
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	26.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	12.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	16.000
	0700- 2-112	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	1.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	2.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	3.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	6.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	3.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	14.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	13.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	201.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,789.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21356045201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,998.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	87.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.037
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	7.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	36.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,208.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.463
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	5.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	18.278
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	1.006
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	18.937
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	18.290
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.596

Call Order: 005 Proposal: T2A52

ALT	Item	Description	Unit	Quantity
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.238
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.129
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.636
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.257
	0713-103-102	PERMANENT TAPE, WHITE, SOLID, 8" EXIT LANE AT INTERCHANGE ON CONCRETE PAVEMENT	GM	0.054
	0713-103-171	PERMANENT TAPE, WHITE, 3-9 DOTTED, 6" WIDE, FOR CONCRETE SURFACES	GM	0.111
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.257
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.257
	0713-103-371	PERMANENT TAPE, BLACK, 3-9 DOTTED, 6" WIDE, FOR CONCRETE SURFACES	GM	0.111
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.257