

Letting:	CT260930	Call Order: 013	Proposal: T5893	District:05
Counties:	VOLUSIA			
Road Name:	SR 483 (CLYDE MORRIS BLVD)			
Limits:	FROM RICHARD PETTY BLVD TO SR 600 (INTERNATIONAL SPEEDWAY BLVD)			

Federal Aid No: D526062B

Total Roadway Length:	0.394 Miles	Contract Days:	230
Total Bridge Length:	0.000 Miles	Letting Date:	09/30/26
Total Proposal Length:	0.394 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30 Days

Proposal Budget Estimate: \$6,566,772.00

Please read the full advertisement

The Improvements under this Contract consist of milling and resurfacing, base work, reconstruction, drainage improvements, curb and gutters, sidewalks, signing and pavement markings, signalization, and lighting on State Road 483 (Clyde Morris Blvd.) from Richard Petty Blvd. to State Road 600 (International Speedway Blvd.) approximately 0.394 miles in Volusia County.

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
0101-	1-	MOBILIZATION (44877325201)	LS	1.000
0102-	1-	MAINTENANCE OF TRAFFIC (44877325201)	LS	1.000
0102-	4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44877325201)	LS	1.000
0102-	14-	TRAFFIC CONTROL OFFICER	HR	1,120.000
0102-	60-	WORK ZONE SIGN	ED	8,565.000
0102-	71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,416.000
0102-	71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	996.000
0102-	74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	22,825.000
0102-	74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	58,297.000
0102-	75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	400.000
0102-	76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	460.000
0102-	78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	794.000
0102-	99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	488.000
0102-	104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	460.000
0102-	107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	460.000
0102-	112-	EXISTING ITS MAINTENANCE	DA	230.000
0102-	115-	TYPE III BARRICADE	ED	480.000
0104-	10- 3	SEDIMENT BARRIER	LF	2,225.000
0104-	11-	FLOATING TURBIDITY BARRIER	LF	31.000
0104-	18-	INLET PROTECTION SYSTEM	EA	27.000
0107-	1-	LITTER REMOVAL	AC	53.500
0107-	2-	MOWING	AC	53.290

Call Order: 013 Proposal: T5893

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (44877325201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	550.000
	0120- 1-	REGULAR EXCAVATION	CY	1,025.000
	0120- 4-	SUBSOIL EXCAVATION	CY	3,449.500
	0120- 6-	EMBANKMENT	CY	26,133.400
	0160- 4-	TYPE B STABILIZATION	SY	553.000
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY	553.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	19,558.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,882.400
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,651.600
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	1.000
	0425- 1-341	INLETS, CURB, TYPE P-4, <10'	EA	2.000
	0425- 1-552	INLETS, DT BOT, TYPE E, >10'	EA	1.000
	0425- 1-553	INLETS, DT BOT, TYPE E, J BOT, <10'	EA	2.000
	0425- 1-583	INLETS, DT BOT, TYPE H, J BOTTOM <10'	EA	5.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	8.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	3.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	3.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	13.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	208.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	16.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	25.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	15.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	268.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	2,819.000
	0430-560-100	STRAIGHT CONCRETE ENDWALLS, 60", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	51.900
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	1,419.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	637.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	383.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	3,513.000
	0527- 2-	DETECTABLE WARNINGS	SF	166.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,885.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	20,813.000
	0591- 1-400	IRRIGATION SLEEVE, 4" DIAMETER	LF	1,203.000
	0591- 1-600	IRRIGATION SLEEVE, 6" DIAMETER	LF	1,203.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.498
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,672.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,732.000

Call Order: 013 Proposal: T5893

ALT	Item	Description	Unit	Quantity
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.715
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.213
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	63.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.077
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	131.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.273
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44877325201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	6.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	3.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	10.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	2.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	724.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44877325201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.124
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,285.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	361.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	258.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.137
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	38.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	105.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.119
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,143.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.525
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.607
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.125
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	998.000

Call Order: 013 Proposal: T5893

ALT	Item	Description	Unit	Quantity
Section 0003 Lighting				
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	2,445.000
	0715- 5- 31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	4.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	8.000
Section 0004 Signalization				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.394
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	3.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	818.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	687.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	75.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	2.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	50.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	12.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	3.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	6.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	3.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	230.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	32.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	3.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 1-123	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	244.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	100.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	5.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	15.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	1.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	7.000

Call Order: 013 Proposal: T5893

ALT	Item	Description	Unit	Quantity
	0650- 1- 36	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 4 SECTION, 1 WAY	AS	2.000
	0650- 1- 39	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 5 SECTION CLUSTER, 1 WAY	AS	1.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	7.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	14.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	1.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	3.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	4.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	11.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	2.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	9.000
	0660- 9- 11	TRAFFIC DATA DETECTION SYSTEM- VIDEO, FURNISH AND INSTALL, CABINET EQUIPMENT	EA	2.000
	0660- 9- 12	TRAFFIC DATA DETECTION SYSTEM- VIDEO, FURNISH AND INSTALL, ABOVE GROUND EQUIPMENT	EA	3.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	1.000
	0663- 1-123	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, CABINET ELECTRONICS	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	14.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	1.000
	0670- 5-161	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA W/STANDARD LOCK, 1 PREEMPTION	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	1.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	1.000
	0678- 1-104	CONTROLLER ACCESSORIES, REPLACE EXISTING- FURNISH AND INSTALL, LOAD SWITCH	EA	1.000
	0682- 1-163	ITS CCTV CAMERA, PRESSURIZED, IP, HIGH DEFINITION	EA	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	3.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	2.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	3.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,101.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	4.000