

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 022	Proposal: T7591	District:07
Counties:	HILLSBOROUGH			
Road Name:	SR 600 (US 92)			
Limits:	FROM EUREKA SPRINGS RD TO THONOTOSASSA RD			
Project(s):	45033915201(*)	Federal Aid No:	D725022B	
Project(s):	45033915601	Federal Aid No:	N/A	
Total Roadway Length:	12.540 Miles	Contract Days:	300	
Total Bridge Length:	0.027 Miles	Letting Date:	10/28/26	
Total Proposal Length:	12.567 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days Flexible	
Proposal Budget Estimate:	\$18,425,000.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of mill and resurface of existing asphalt pavement, replace sidewalk slabs, install new sidewalk and gravity wall, install pier protection barriers at the I-75 overpass, replace guardrail, install signing and pavement markings and miscellaneous signalization improvements on US 92 / SR 600 from Eureka Springs Rd to Thonotosassa Rd in Hillsborough County.

Call Order: 022 Proposal: T7591

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45033915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45033915201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45033915201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	840.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,152.000
	0102- 60-	WORK ZONE SIGN	ED	28,900.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	696.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	732.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	24,725.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,409.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	684.000
	0102-115-	TYPE III BARRICADE	ED	4,800.000
	0104- 10- 3	SEDIMENT BARRIER	LF	18,441.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	21.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	35.000
	0107- 1-	LITTER REMOVAL	AC	182.800
	0107- 2-	MOWING	AC	91.400
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (45033915201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45033915201)	LS	1.000

Call Order: 022 Proposal: T7591

ALT	Item	Description	Unit	Quantity
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,518.000
	0110- 86-	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT (45033915201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	550.000
	0120- 6-	EMBANKMENT	CY	250.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	277.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	45.200
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	217,605.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	78,063.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	3,118.600
	0334- 1- 59	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, HIGH POLYMER	TN	14,836.700
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC E, FC-12.5, PG 76-22	TN	3,190.500
	0337- 7- 95	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC E, FC-12.5, HIGH POLYMER	TN	21,510.700
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	232.300
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	96.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	1.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	6.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	3.000
	0425- 5-	MANHOLE, ADJUST	EA	14.000
	0425- 6-	VALVE BOXES, ADJUST	EA	10.000
	0425- 82-	REPLACE GRATE	EA	2.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	309.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	38.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	42.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	10.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	312.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	9.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	59.000
	0430-530-100	STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	1.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	2.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	9.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	116.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	32.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	9.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	3.000
	0430-984-633	MITERED END SECT, OPTIONAL /ELLIP/ARCH, 30" SD	EA	1.000
	0431- 1-530	PIPE LINER, SLIPLINING, 30"	LF	81.000
	0515- 1- 1	PIPE HANDRAIL - GUIDERAIL, STEEL	LF	498.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	503.000

Call Order: 022 Proposal: T7591

ALT	Item	Description	Unit	Quantity
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	83.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	525.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,648.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,047.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	22.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,680.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	4,515.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	2,736.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	3.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	33.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	3.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,405.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	34,681.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	725.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	16.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	16.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	5.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	55.244
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.120
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	16,064.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,038.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	15,202.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	5.070
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	486.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	53.190
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	3,394.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.812
	0770- 2- 12	MCSAW VEHICLE DETECTION AND IDENTIFICATION - FURNISH AND INSTALL, WEIGH IN MOTION UNIT	AS	2.000
	0770- 2- 13	MCSAW VEHICLE DETECTION AND IDENTIFICATION - FURNISH AND INSTALL, INDUCTIVE LOOP ASSEMBLY	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45033915201)	LS	1.000

Call Order: 022 Proposal: T7591

ALT	Item	Description	Unit	Quantity
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	24.424
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	40.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	5.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	3.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	324.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	323.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	76.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	615.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	16.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,965.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45033915201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	519.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,840.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	2.535
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	243.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,697.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.906
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	8,032.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	5,761.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	27.622
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.060
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	26.595
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.610
Section 0003 Signalization				
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	3,600.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	3,600.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	300.000
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	2.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	517.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,457.000

Call Order: 022 Proposal: T7591

ALT	Item	Description	Unit	Quantity
	0630- 2- 17	CONDUIT, FURNISH & INSTALL, OPEN TRENCH UNDER PAVEMENT	LF	290.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	8.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	8.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	300.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	67.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	67.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	36.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	75.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	67.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	8.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	14.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	67.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	8.000
	0682- 1-163	ITS CCTV CAMERA, PRESSURIZED, IP, HIGH DEFINITION	EA	2.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	5.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	5.000
Section 0004 Utilities				
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	14.000
	1050- 51-212	UTILITY PIPE- DUCTILE IRON/CAST IRON, FURNISH & INSTALL, WATER/SEWER, 12"	LF	16.000
	1055- 51-112	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 12"	EA	4.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	4.000
	1080- 21-112	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 12"	EA	1.000
	1080- 21-500	UTILITY FIXTURE, VALVE/METER BOX, ADJUST	EA	7.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	1.000
	1080- 29-112	UTILITY FIXTURE, MECHANICAL JOINT RESTRAINT, FURNISH & INSTALL, 12"	EA	12.000
	9999- 26-	CONTINGENCY SA (Sixth) (SM Only) (45033915601)	LS	1.000