

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT260325 Call Order: 015 Proposal: T3939 District:03

Counties: WASHINGTON

Road Name: CR 173 (BETHEL RD)

Limits: OVER GUM CREEK NO 2, BRIDGE NO 610026

Project(s): 44907815201(*) Federal Aid No: D325043B

Total Roadway Length:	0.135 Miles	Contract Days:	180
Total Bridge Length:	0.000 Miles	Letting Date:	03/25/26
Total Proposal Length:	0.135 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30 Days

Proposal Budget Estimate: \$1,789,655.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of pavement reconstruction, guardrail, drainage improvements, bridge culvert removal (No. 610026), bridge culvert construction (No. 614175), single slope barrier / junction slab - wall coping, and pavement markings on CR 173 Bethel Road over Gum Creek No. 2 Bridge No. 610026 in Washington County.

Call Order: 015 Proposal: T3939

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44907815201)	LS	1.000
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	223.800
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	39,687.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	98.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	564.500
	0530- 74-	BEDDING STONE	TN	210.200
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	196.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	4.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44907815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44907815201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	25.500
	0102- 60-	WORK ZONE SIGN	ED	5,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,552.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	388.000
	0102-115-	TYPE III BARRICADE	ED	720.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,277.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	278.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	390.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0110- 1- 1	CLEARING & GRUBBING (44907815201)	LS	1.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	1.000
	0120- 1-	REGULAR EXCAVATION	CY	1,235.300

Call Order: 015 Proposal: T3939

ALT	Item	Description	Unit	Quantity
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,157.600
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	268.700
	0160- 4-	TYPE B STABILIZATION	SY	2,744.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	353.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,805.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	67.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	153.500
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	174.100
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	42.900
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	19.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	2.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	462.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	283.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,243.000
Section 0003 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	36.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44907815201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.270
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.270