

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251029	Call Order: 008	Proposal: T3946	District:03
Counties:	SANTA ROSA			
Road Name:	SR 87			
Limits:	FROM N OF SR 4 TO ALABAMA STATE LINE			
Project(s):	45081515201(*)	Federal Aid No:	D325052B	
Total Roadway Length:	7.026 Miles	Contract Days:	185	
Total Bridge Length:	0.000 Miles	Letting Date:	10/29/25	
Total Proposal Length:	7.026 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	

Proposal Budget Estimate: \$2,598,247.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing SR 87 from N of SR 4 to Alabama State Line. Other work consists of pavement reconstruction, drainage improvements and signing and pavement markings. The project location is Santa Rosa County.

Call Order: 008 Proposal: T3946

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45081515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45081515201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	21,645.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	25,457.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	398.000
	0102-115-	TYPE III BARRICADE	ED	370.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	185.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,930.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	456.640
	0107- 2-	MOWING	AC	406.980
	0110- 1- 1	CLEARING & GRUBBING (45081515201)	LS	1.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (45081515201)	LS	1.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,932.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	133,740.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	117.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	9.600
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	11,048.800
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	69.200
	0530- 74-	BEDDING STONE	TN	37.300
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	20,044.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,329.000

Call Order: 008 Proposal: T3946

ALT	Item	Description	Unit	Quantity
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	13.843
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	187.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.125
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	5.039
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45081515201)	LS	1.000
Section 0002 Signing				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	1.000
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	19.676
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	10.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	8.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	13.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,329.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45081515201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	187.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	13.843
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.125
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	5.039