

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250611	Call Order: 003	Proposal: T3950	District:03
Counties:	OKALOOSA			
Road Name:	SR 85 (N FERDON BLVD)			
Limits:	AT JONES RD			
Project(s):	45331915201(*)	Federal Aid No:	D324009B	
Total Roadway Length:	0.095 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	06/11/25	
Total Proposal Length:	0.095 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	

Proposal Budget Estimate: \$1,262,004.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of drainage improvements, highway signing and other incidental construction on SR 85 N Ferdon Blvd. at Jones Road Outfall Repair Project (FPID:453319-1-52-01) in Okaloosa County.

Call Order: 003 Proposal: T3950

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45331915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45331915201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	720.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	93.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,897.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	119.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	1.000
	0110- 1- 1	CLEARING & GRUBBING (45331915201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	16.000
	0120- 1-	REGULAR EXCAVATION	CY	1,171.100
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	12,679.800
	0425- 1-544	INLETS, DITCH BOTTOM, TYPE D, J BOT, >10'	EA	1.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	1.000
	0430-174-136	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	LF	116.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	8.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	232.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	1.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	20.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	434.800
	0530- 74-	BEDDING STONE	TN	306.200
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	9,260.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	1,910.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45331915201)	LS	1.000