

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT261028	Call Order: 014	Proposal: T3A08	District:03
Counties:	JACKSON			
Road Name:	SR 2 FROM SPRING BRANCH TO E OF COWARTS CREEK BRIDGE			
Limits:	53070000			
Project(s):	45294315201(*)	Federal Aid No:	D326041B	
Total Roadway Length:	4.052 Miles	Contract Days:	120	
Total Bridge Length:	0.318 Miles	Letting Date:	10/28/26	
Total Proposal Length:	4.370 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days Flexible	
Proposal Budget Estimate:	\$1,763,494.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of FPID 452943-1-52-01 the resurfacing of SR 2 from Spring Branch to east of Cowarts Creek Bridge in Jackson County. Existing travel lanes and paved shoulders will be resurfaced. Other improvements include upgrades to signing & pavement markings.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 014 Proposal: T3A08

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45294315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45294315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,436.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	41,272.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	891.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	508.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	120.000
	0107- 1-	LITTER REMOVAL	AC	143.320
	0107- 2-	MOWING	AC	143.320
	0110- 1- 1	CLEARING & GRUBBING (45294315201)	LS	1.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	57,014.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	17,757.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	333.200
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	7,902.800
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	12,632.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.132
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	3.241
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45294315201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	12.030
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	19.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	891.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45294315201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	7.998
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.132
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	3.241
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.674
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.107
	0713-103-281	PERMANENT TAPE, YELLOW, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.337