

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting:	CT250924	Call Order: 007	Proposal: T4721	District:04
Counties:	BROWARD			
Road Name:	SR 811 (DIXIE HWY)			
Limits:	FROM N OF SR 816 (OAKLAND PARK BLVD) TO NE 44TH ST (PROSPECT RD)			
Project(s):	44927815201(*)	Federal Aid No:	D425021B	
Project(s):	44927815202	Federal Aid No:	D425021B	
Total Roadway Length:	1.091 Miles	Contract Days:	140	
Total Bridge Length:	0.000 Miles	Letting Date:	09/24/25	
Total Proposal Length:	1.091 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	45 Days	
Proposal Budget Estimate:	\$971,600.00			

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of, but are not limited to, construction of lighting improvements (installation of new light poles, luminaire retrofits, placement of conduits, pull boxes, pole cable distribution, and conductors), and incidental reconstruction of concrete sidewalks along State Road 811 (Dixie Highway) from North of SR 816/Oakland Park Boulevard to NE 44th Street/Prospect Road, for a total of 1.091 miles in the City of Oakland Park, in Broward County

**BUSINESS DEVELOPMENT INITIATIVE** -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <https://www.fdot.gov/equalopportunity/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at <https://www.fdot.gov/construction/training/ctqp/smallbusiness/smallbusinessstraining.shtm>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: [fdot.bdi@dot.state.fl.us](mailto:fdot.bdi@dot.state.fl.us).

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the File Attachment Upload folder in the AASHTOWare Project Bids application.

BDI Reference Sheet may be found at: <https://www.fdot.gov/equalopportunity/bdi.shtm>

Proposal Guaranty of \$500 is required for bids over \$150,000 and may be in the form of a Cashiers Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

**Call Order: 007 Proposal: T4721**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44927815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44927815201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44927815201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	144.000

**Call Order: 007 Proposal: T4721**

ALT	Item	Description	Unit	Quantity
	0102- 60-	WORK ZONE SIGN	ED	4,900.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,000.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	78,924.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	200.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	428.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44927815201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	342.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	104.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	218.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	9.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44927815201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	3.000
<b>Section 0003 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	244.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	802.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	36.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	17,711.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,180.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	17,404.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	2.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	25.000
	0715- 61-352	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 15' ARM LENGTH	EA	14.000
	0715- 62-352	LIGHT POLE COMPLETE, F&I, STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT, 15' ARM LENGTH	EA	3.000
	0715- 65-266	LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 16' ARM LENGTH	EA	2.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	46.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (44927815202)	LS	1.000
<b>Section 0004 Intelligent Transportation System</b>				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	140.000